
MAINTENANCE CRAFT ARTICLE 12 GUIDE

August 2022



GETTING STARTED WITH ARTICLE 12 IMPACTS

INFORMATION REQUESTS/STAFFING PACKAGES

Presented by:
HQ Assistant Director, Jason Treier and NBA Hector Baez


Mark Dimondstein
President

Idowu Balogun
Maintenance Director

v 3.0

MAINTENANCE DIVISION RESIDENT OFFICERS

1300 L Street, NW Washington, D.C. 20005
(202) 842-4213 (202) 289-3746 (Fax)

	**Terry B. Martinez** **Assistant Dir. A**		**Idowu Balogun** **National Director**		**Jason Treier** **Assistant Dir. B**

MAINTENANCE DIVISION NATIONAL BUSINESS AGENTS

Central Region		Central Region		Central Region	
	**Craig Fisher -A** 1435 Research Park Drive Dayton, OH 937-320-9454 (P) 937-277-4855 (F)		**Jeff Beaton - B** 10841 W. 87th St Suite 400 Overland Park, KS 913-888-8555 (P) 913-888-8777 (F)		**Curtis Walker - C** 8009 34th Ave Suite 1050 Bloomington, MN 952-854-0093 (P) 952-854-0268 (F)
Southern Region		**Southern Region**		**Eastern Region**	
	**John Gearhard -A** 6951 Pistol Range Rd, Suite 106 Tampa, FL 813-855-7023 (P) 813-855-7567 (F)		**Carlos Paz - B** 800 W Airport Fw LB 6093, St 1031 Irving, TX 972-721-0063 (P) 972-579-5571 (F)		**Kenneth Lester** 1401 Liberty Place Sicklerville, NJ 856-740-0115 (P) 856-740-0731 (F)
Western Region		**Western Region**		**Northeast Region**	
	**Hector Baez - A** 1255 W Baseline Rd, Suite D-190 Mesa, AZ 480-777-1880 (P) 480-777-1886 (F)		**Louis Kingsley - B** 150 E Colorado Blvd, Suite 208 Pasadena, CA 626-585-1404 (P) 626-585-0091 (F)		**Dave Sarnacki** 2 Electronics Ave, Suite 38 Danvers, MA 978-777-8692 (P) 978-777-7419 (F)
Pacific Area NBA		**Caribbean Area NBA**		**Alaskan Area NBA**	
	**Rufina Pagaduan** 949 Kapiolani Blvd, Suite 101 Honolulu, HI 808-589-1178 (P) 808-589-2551 (F)		**Daniel Soto** Calle 42 S E 1000 Reparto Suite 202 Rio Pledras, PR 787-758-7985 (P) 787-250-8376 (F)		**James Patarini** Post Office Box 210021 Anchorage, AK 907-333-6356 (P)

TABLE of CONTENTS

Chapter 1 - Article 12/Excessing Introduction ……. p 4

Chapter 2 – Submitting Information Requests …… p 5

Chapter 3 – eWHEP/Mechanized Staffing Package …….. p 7

Chapter 4 – MS-1/Building-side Staffing Package ……. p 16

Chapter 5 – Field Maintenance Staffing Package …….. p 43

Chapter 6 – Maintenance Support Clerk Staffing ……... p 48

Chapter 7 – Maintenance Vacancies & Article 38.3.K.4 …… p 50

Chapter 8 – Overtime Usage and the CWHR……. p 51

Chapter 9 – Miscellaneous Mitigating Factors ……. p 52

Chapter 1 - Article 12/Excessing Introduction

When the Postal Service determines that there are too many maintenance employees in a section, facility or installation, they invoke the involuntary reassignment (referred to as *excessing*) provisions of Article 12.

When implementing Article 12.5.C.5 (Reduction in the Number of Employees in an Installation Other Than by Attrition), management's first course of action is to notify the regional coordinator (in writing), identifying the impacted installation, occupational group(s) and number of employees. These notifications are commonly called *Impact Statements*. Article 12 area/regional level meetings are required no less than 90 days (six months if possible) in advance of any anticipated reassignments outside an installation.

After the regional notification, local/state unions are notified. Information requests must be submitted to verify the accuracy of management's excessing data. The validity of the impact and ways to mitigate it are discussed at the regional meeting(s).

The first step in confirming management's data is to request and obtain copies of the applicable maintenance staffing packages relied on. Most staffing packages include inventory documents that must be analyzed:

1. eWHEP (Electronic Work Hour Estimator Program) is the program the USPS uses to estimate maintenance work hours and determine the overall number of positions for a Maintenance Department. eWHEP staffing packages are comprised of several sections, one for each functional maintenance area, including the Mail Processing Equipment module which determines ET, MPE and machine-side MM7 staffing. This machine-side staffing is based on the LDC 36 inventory and annual staffing hours. eWHEP encompasses the data of all the different maintenance staffing packages.

2. MS-1 staffing packages contain inventory and annual staffing hours for LDC 37 employees who perform the building and building equipment (BEM, MM7) work.

3. Field Maintenance staffing packages include historical data recorded by Field Maintenance employees (AMTs, AMSs) over the last 13 accounting periods.

4. Maintenance Support Clerk staffing is determined by applying the staffing matrix in MMO-102-18 and is based on the number of supported Maintenance Craft positions.

5. MS-47 staffing packages are comprised of several forms that determine custodial staffing.

Chapter 2 – Submitting Information Requests

The most critical aspect of an Article 12 investigation is the submission of information requests and obtaining requested information. Subsequent chapters in this guide explain the reason for specific information requests and what to look for once the information is furnished. The importance of requesting and analyzing these documents for accuracy and pointing out deficiencies cannot be overstated. Impacted sites must know what equipment is (and is not) within the installation.

The following must be requested based on local fact circumstance:

- Depending on which occupational groups are impacted, request a copy of the current, approved staffing package (to include all forms). Management's impact statement will determine whether to RFI the eWHEP, MS-1, Field Maintenance or Custodial staffing packages (or combinations thereof).

- Copies of the most current eMARS Staffing Worksheets for all mail processing equipment within the installation.

- Copy of the Site Staffing Package History. This identifies which local and area management officials submitted/rejected the locally created/proposed MS-1 staffing packages and the dates the staffing packages were rejected.

- Copies of all locally created/proposed MS-1 staffing packages identified in the MS-1 Site Staffing Package History.

- Copies of all emails (sent and received) between local, district and area management regarding the proposed MS-1 staffing packages and their rejections.

- Interview every local postal official who played a role in creating the local/proposed MS-1 staffing packages.

- Identify all vacant maintenance craft duty assignments within the installation.

- Identify the number of maintenance employees currently on the rolls, by occupational group.

- Identify all mail processing and building equipment that has been added or removed from the installation within the past two years.

- If any mail processing equipment and/or building equipment was added or removed within the past two years, determine when it was added or removed. If exact dates are

unknown, please approximate.

- Identify which occupational group has historically performed the building maintenance work in stations and branches.

- Copies of all reports, documents, daily work assignment sheets, eMARS reports, everything, etc., that identifies the occupational group that has historically performed building maintenance work in stations and branches.

- Identify whether field maintenance employees have begun performing building maintenance work in stations and branches and, if so, when field maintenance employees began performing this work.

- Copies of overtime reports illustrating the number of overtime and penalty overtime hours used in the past twelve months for all affected occupational groups.

- Identify all ill/injured employees from other crafts that are reassigned into and are currently working in the maintenance craft within the installation.

- Identify all maintenance craft employees within the installation that have pending eReassign transfer requests to transfer outside the installation (and identify which installations the aforementioned employees have transfer requests to).

- Identify all retirement-eligible maintenance craft employees within the installation.

A copy of the Local Memorandum of Understanding (LMOU) should be available for the purposes of identifying applicable sections within the local. Also, remember that there is no Abolishment language in Article 38.

**** Note** – It is important to submit the information requests more than once. Following the initial submission, wait no later than a week (or whatever time frame a mutual agreement or LMOU dictates) before submitting a second request. Notate on the RFI(s) that it is the second request. In addition to submitting the second RFI to the installation head/designee, copy that official's superior (i.e., plant manager, senior plant manager, district labor relations). If the information is not provided after the second request, file an Article 17.3/31.3 violation grievance and an NLRB unfair labor practice charge, if need be depending on fact circumstances. This is important because it demonstrates the union is serious about acquiring the requested information should this grievance (or any subsequent Article 12/staffing grievances) go to arbitration.

Chapter 3 – eWHEP/Mechanized Staffing Package

As previously stated, eWHEP staffing packages contain the inventory and annual staffing hours for LDC 36 employees who work on mail processing equipment (ETs, MPEs, MM7s). Most of the annual staffing hours for eWHEP/mechanized staffing is based on the Maintenance Management Orders (MMOs) for each individual piece of mail processing equipment.

STEP-1: IDENTIFYING ADDITION OR REDUCTION OF MAIL PROCESSING EQUIPMENT

A very common cause of reduction in LDC 36 employees is the removal/relocation of mail processing equipment from an installation. It is unfortunate but reasonable that a reduction in mail processing equipment results in a reduction in the maintenance employee complement.

Conversely, it is sensible that the addition of mail processing equipment increases staffing. Be sure to investigate and identify any mail processing equipment removed or added to the installation within the past few years.

STEP-2: VERIFYING THE ACCURACY OF THE eWHEP/MECHANIZED INVENTORY

The first step after receiving a copy of the current, approved eWHEP staffing package is to verify the mechanized inventory.

The eWHEP mechanized staffing documents includes sections 2A (Miscellaneous Postal Equipment), 2B (Major Mechanization/Automation) and worksheet 2C (Additional Requirements).

Section 2B inventory is usually the easiest to confirm because it tends to be most visible. If the installation has 6 DIOSS machines, ensure the 2B inventory lists 6 DIOSS machines. If the installation has 2 APBS machines, ensure the 2B inventory lists 2 APBS machines, and so on.

The same goes for 2A inventory, which is commonly smaller (and sometimes portable) equipment, like strapping machines and portable conveyers. The current MMO for each piece of equipment establishes the maintenance hours.

Section 2C lists new equipment that does not have an MMO yet. It is also where locally purchased items pertaining to mail processing are listed and items with updated MMOs that the eWHEP program has not yet accounted for.

STEP-3: ANALYZING THE eMARS STAFFING WORKSHEETS FOR OPERATIONAL TOURS

The next step is to review the eMARS Staffing Worksheets for the installation mail processing equipment. These documents show information such as: (1) number of days per week a machine operates, (2) number of tours per day a machine runs, (3) number of stackers per machine, etc.

A common occurrence is the misrepresentation of the number of tours that mail processing equipment operates. Management used to manually enter the number of tours machines operated. Currently, eMARS auto-populates the tour field resulting in fewer reported tours. In some cases, machines operating on all three tours are flagged as only operating on one or two tours.

The applicable machine MMO provides staffing hour calculations partially based on the number of operating tours. Employee statements, management interviews and machine run-time reports will reveal the actual number of machine operating tours, as will the clerk and mail handler weekly work schedules. This challenge must be supported by substantial/concrete evidence that the mail processing equipment operates for more tours than the eMARS Staffing Worksheets account for.

SAMPLE eWHEP STAFFING DOCUMENTS AND eMARS STAFFING WORKSHEETS

Please find enclosed samples of eWHEP forms and eMARS documents; this is not a complete eWHEP package for the location.

NORFOLK VA PDC

600 CHURCH STREET

NORFOLK, VA. 23501-9990

STAFFING WORKSHEET (W-140)

DELIVERY BAR CODE SORTER PH 2-5 ICS-OSS PARS (DBCS_CI)

MMO-017-13

Equipment Number	No. of Tours	No. Stackers	Days-Wk	Pieces Fed	MM5/MM6	MM-7	MPE-9	ET-10	Total Hours	Operational Maintenance Hours
1	1	254.00	7	88936929	0.00	1,006.32	527.60	428.51	1,962.43	315.47
2	1	254.00	7	51595352	0.00	870.77	432.01	405.95	1,708.73	315.47
3	1	254.00	7	58980951	0.00	897.52	450.81	410.39	1,758.71	315.47
24	1	254.00	7	52226304	0.00	873.11	433.55	406.35	1,713.01	315.47
				Total	0.00	3,647.72	1,843.97	1,651.20	7,142.88	1,261.88

SECTION 2-A

NORTHERN VA PDC

LAST STAFFING PACKAGE APPROVAL DATE
September 7, 2019 8:15 AM

WORKHOUR ESTIMATE PROGRAM
MISCELLANEOUS POSTAL EQUIPMENT

Acronym	Class	Equipment Description (Qualifying Remarks) Miscellanous Postal Equipment	Reference Document(s)	Annual Workhours Auth/Unit	Unit Inventoried	Annual workhours
AHMR	AA	Apartment House Mail Receptacle All Types and Models -	see Historical Data	0.0	0	0.0
BATTERY	AA	Batteries - Use Historical Data	see Historical Data	0.0	0	3291.0
BLDG	MM	Cabinet Filing Letter-Legal - All Sizes Item Nos. - 434 4		0.1	0	0.0
BLDG	MM	Cabinet Storage Item No. 212-B or Equivalent		0.1	0	0.0
BLDG	MM	Locker Clothing - All Sizes Item Nos. 302-B1 B2 B3 B4		0.0	625	12.5
BLDG	MM	Recorder Time (Simplex or Cincinnati)		15.0	0	0.0
BOX	BA	Box Relay Item No. 1171-K	Pub 247	1.0	0	0.0
BOX	AA	Collection Box (Contract Repair)	Pub 247	1.0	0	0.0
BOX	AA	Collection Box (Repaired In-House)	Pub 247	2.0	0	0.0
BOX	CA	Express Mail Boxes - All Types	Pub 247	2.0	0	0.0
BOX	DA	Mail Chute		1.0	0	0.0
CANX	AA	Canceler Class A B (Seasonal Use Only)		10.0	0	0.0
CANX	AA	Canceling Machines All Models (Except Flats)	Pub 247	125.0	4	500.0
CBU	AA	CLUSTER BOX UNIT	see Historical Data	0.0	0	0.0
CCTV	AA	Closed Circuit TV Camera - All Models	MMO-056-98	1.1	0	0.0
CCTV	AB	Closed Circuit TV Monitor - All Models	MMO-057-98	1.1	0	0.0
CONT	ZZ	Container Post Con Item No. 3907		1.5	0	0.0
CONT	ZZ	Container Wire Mesh Item Nos. 1932-A (60 in. height) 19		1.6	0	0.0
CONT	BJ	Containers In House A-Frame Tray Cart--1226D		0.5	0	0.0
CONT	BE	Containers In House BMC Container--3924		1.0	0	0.0
CONT	BB	Containers In House Hamper--1033	Pub 247	0.3	0	0.0
CONT	BA	Containers In House Hamper--1046	Pub 247	1.0	0	0.0
CONT	BI	Containers In House Seven-Shelf Tray Cart--1226C		0.5	0	0.0
CONT	BD	Containers In House Utility Cart--1075	Pub 247	0.4	0	0.0
CONT	AA	Containers Over the Road Aluminum OTR--3910 (Alum)	Pub 247	2.1	0	0.0
CONT	AK	Containers Over the Road Con-Con Security-- 3920		0.4	0	0.0
CONT	AE	Containers Over the Road ERMC--3921		1.6	0	0.0
CONT	AD	Containers Over the Road GPMC 3909	Pub 247	1.5	0	0.0
CONT	AI	Containers Over the Road Mesh Container--1923B		1.6	0	0.0

SECTION 2-A

CONT	AJ	Containers Over the Road Reg Mail--Bonus Built		1.6	0	0.0
CONT	ZZ	Security Container - All Models Item Nos. 293 295 296 2		2.5	0	0.0
DOCKS	AA	Docksramp-Flipramp-Dockleveler or Equivalent (Do not in		16.0	0	0.0
FLATS	AA	Flats Canceler All Types Models		6.0	0	0.0
FMPCS	AA	Fixed Mechanization Process Control System	MMO-137-98	5.1	0	0.0
HDUMP	AA	Hamper Dumper All Types and Models	MMO-065-02	17.3	8	138.4
MOPE	AL	Clark Forklift (All Models)	MMO-069-17	50.0	0	0.0
MOPE	AM	Crown Forklift (All Models)	MMO-069-17	50.0	0	0.0
MOPE	CD	Crown Pallet Truck (All Models)	MMO-069-17	50.0	0	0.0
MOPE	AN	Hyster Forklift (All Models)	MMO-069-17	50.0	0	0.0
MOPE	EA	Mobile OP EQ-Mini Lift FSS Only	MMO-069-17	1.0	0	0.0
MOPE	AA	Mobile OP Eq Forklift Ride Or Walk Motorized		50.0	20	1000.0
MOPE	CA	Mobile OP Eq Pallet Truck Motorized - Non Motorized		1.0	13	13.0
MOPE	BA	Mobile OP Eq Tow Tractor Tugger Power Ox		52.0	11	572.0
MOPE	DA	Mobile Operating Equipment Other		1.0	7	7.0
MOPE	BD	Taylor Dunn (All Models)	MMO-069-17	52.0	0	0.0
MOPE	AB	Toyota Forklift Model 5	MMO-069-17	50.0	0	0.0
MOPE	AC	Toyota Forklift Model 6	MMO-069-17	50.0	0	0.0
MOPE	AD	Toyota Forklift Model 7	MMO-069-17	50.0	0	0.0
MOPE	AE	Toyota Forklift Model 8	MMO-069-17	50.0	0	0.0
MOPE	CB	Toyota Riding Pallet Truck (All Models)	MMO-069-17	50.0	0	0.0
MOPE	BC	Toyota Tow Tractor (All AC Models)	MMO-069-17	52.0	0	0.0
MOPE	BB	Toyota Tow Tractor (All DC Models)	MMO-069-17	52.0	0	0.0
MOPE	CC	Toyota Walking Pallet Truck (All Models)	MMO-069-17	50.0	0	0.0
MOPE	AO	Yale Forklift (All Models)	MMO-069-17	50.0	0	0.0
NDCBU	AA	Use Historical Data	see Historical Data	0.0	0	0.0
PLOCK	AA	Parcel Locker - All Types - Use Historical Data	see Historical Data	0.0	0	0.0
POBOX	AA	Post Office Lobby Boxes All Types Models		0.0	0	0.0
PPC	AA	Conveyor Portable (Powered) All Other Except Model CF	MS-58	10.0	0	0.0
PPC	AA	Conveyor Portable Aluminum Model L Item Nos. 1920-A	MS-58	10.0	0	0.0
PPC	AA	Conveyor Portable Single-Tilt Model H Item Nos. 1921-A	MS-58	10.0	0	0.0
PPC	AA	Conveyor Portable Powered Model CF-89 All	MMO-005-01	19.1	0	0.0
RACK	AB	DBCS Pie Racks - Use Historical Data	see Historical Data	0.0	0	313.0
RACK	AA	Rack Pouch-Sack - With Casters Item Nos. - Multiple		1.0	0	0.0

SECTION 2-A

RACK	AA	Rack Pouch-Sack - Without Casters Item Nos. - Multiple		0.1	0	0.0
RCOOP	AA	Rack Mailing Co-op (2- or 3- hole)		0.5	0	0.0
SAFES	AA	Vault Door (All Models-Types)		2.5	0	0.0
SCALE	AA	Scale Digital Floor Platform Dock and Manual Scales; A	Pub 247	3.0	0	0.0
SCALE	AA	Scale Portable Platform 1000-2000 lb Item Nos. 0-855	Pub 247	5.0	0	0.0
SCALE	AA	Scale over 500 lb (Except MODSS)	Pub 247	5.0	0	0.0
SSPU	HA	Self Service Postal Unit Structure Housing		250.0	0	0.0
SSPU	HA	Self-Service Postal Center (SSPC) Drive-Up Unit (Structu		250.0	0	0.0
SSPU	HA	Self-Service Postal Center (SSPC) Screen-Line Unit		100.0	0	0.0
SSPU	HA	Self-Service Postal Center (SSPC) Walk-Up Unit		200.0	0	0.0
STRAP	AA	Strapping Machine All Types Models	Historical Data	120.0	0	0.0
VEND	AA	Machine Stamp Vending - All Models (Claim only if not ma		19.0	0	0.0
					Total	5846.90

SECTION 2-B

NORTHERN VA PDC

MAINTENANCE WORKHOUR ESTIMATE PROGRAM
MAJOR MECHANIZATION/AUTOMATION

Acronym	Class Code	Equipment Description (Qualifying Remarks) Miscellanous Postal Equipment	Reference Document(s)	Worksheet Number	Unit Invent-oried	Annual workhours
AFCS200	AA	ADVANCED FACER CANCELER SYSTEM 200	MMO-149-15	See W-301 Worksheet	5	8,472.75
AFSM100	AC	AUTOMATED FLAT SORTING MACHINE 100 - FICS-ATHS	MMO-095-12	See W-35 Worksheet	1	1,359.52
AFSM100	AE	AUTOMATED FLAT SORTING MACHINE 100 - FICS-ATHS-FPARS	MMO-095-12	See W-37 Worksheet	1	2,096.61
AFTL	AA	AUTOMATIC FLATS TRAY LIDDER	MMO-023-10	See W-34 Worksheet	1	174.60
AIAFSM	AA	AUTOMATIC INDUCTION AFSM100. GRP_CODE from M to N in 7-JAN-2019	MMO-100-12	See W-161 Worksheet	2	1,904.00
APBS	AA	AUTOMATED PARCEL BUNDLE SORTER	MMO-090-16	See W-300 Worksheet	1	2,801.44
ASD	CA	AUTO SEAMLESS DISPATCH MOSCA BANDER	MMO-054-06	See W-13 Worksheet	6	1,438.80
ATSII	AA	AUTOMATIC TRAY SLEEVER (2005 CONTRACT BUY)	MMO-132-11	See W-15 Worksheet	1	673.44
ATU	AA	AUTOMATIC TRAY UNSLEEVER	MMO-017-16	See W-16 Worksheet	1	731.15
BDS	AA	BIOHAZARD DETECTION SYSTEM	MMO-046-10	See W-160 Worksheet	7	830.54
CFPS	AA	CHANGE OF ADDRESS FORMS PROCESSING SYSTEM AT CFS UNIT	MMO-131-06	See W-58 Worksheet	1	75.93
CFS	FA	COMPUTERIZED FORWARDING SYSTEM-FLATS FORWARDING TERMINAL	MMO-124-12	See W-3 Worksheet	15	2,655.45
CFS	GA	COMPUTERIZED FORWARDING SYSTEM-FORWARDING CONTROL SYSTEM	MMO-124-12	See W-3 Worksheet	1	98.67
CIOSS	AB	DBCS COMBINE I-O SUB SYS OCR REPLACEMENT (CIOSS C)	MMO-015-13	See W-41 Worksheet	1	3,943.24
DBCS	BA	DELIVERY BAR CODE SORTER PHASE 6	MMO-049-16	See W-44 Worksheet	1	1,683.66
DBCS	CI	DELIVERY BAR CODE SORTER PH 2-5 ICS-OSS PARS	MMO-017-13	See W-140 Worksheet	6	14,072.27
DBCS	CJ	DELIVERY BAR CODE SORTER PHASE 2 - 5 PARS MODIFIED	MMO-050-16	See W-4 Worksheet	7	13,414.15
DIOSS	AC	DBCS I-O SUB SYS (DIOSS B)	MMO-126-16	See W-41 Worksheet	1	3,208.94
DIOSS	AE	DBCS I-0 SUB SYS EXT CAP (DIOSS D)	MMO-019-13	See W-135 Worksheet	1	1,875.92
DIOSS	AF	DBCS I-0 SUB SYS (DIOSS E)	MMO-140-12	See W-136 Worksheet	4	11,743.26
DPRC	AA	DUAL PASS ROUGH CULL	MMO-006-01	See W-5 Worksheet	2	1,187.60
EAA	AA	ENHANCED AIRLINE ASSIGNMENT - ACCUSORT	MMO-124-06	See W-17 Worksheet	2	506.00

SECTION 2-B

MAINTENANCE WORKHOUR ESTIMATE PROGRAM
MAJOR MECHANIZATION/AUTOMATION

Acronym	Class Code	Equipment Description (Qualifying Remarks) Miscellanous Postal Equipment	Reference Document(s)	Worksheet Number	Unit Invent-oried	Annual workhours
FICS	AA	FLATS IDENTIFICATION CODE SORT	MMO-039-15	See W-320 Worksheet	1	34.80
FRES	AA	FLATS REMOTE ENCODING SYSTEM (AFSM100 ONLY) AT PDC	MMO-126-12	See W-303 Worksheet	1	31.94
ICS	BA	IDENTIFICATION CODE SORT- SECONDARY ID CODE SERVER (SICS)	MMO-054-10	See W-166 Worksheet	1	1.53
IJCAFSM	AA	INK JET CANCELER AFSM 100	MMO-127-12	See W-306 Worksheet	1	395.71
IPSS	BA	IMAGE PROC. SUBSYS-ECA AT P-D-TYPE B	MMO-018-15	See W-412 Worksheet	1	380.95
LAN	AA	LOCAL AREA NETWORK-MAIL PROCESS INFRASTR	MMO-056-13	See W-54 Worksheet	1	228.52
LCREM	AA	LOW COST REJECT ENCODING MACHINE	MMO-040-13	See W-338 Worksheet	1	1,265.25
LCTS	CA	LOW COST TRAY SORTER - CARTER CONTROLS	MMO-077-15	See W-900 Worksheet	2	2,349.82
LMS	AA	LOOSE MAIL SYSTEM -AFCS	MMO-061-08	See W-48 Worksheet	1	810.81
LMS	BA	LOOSE MAIL SYSTEM SPBM FEED-LOCKHEED MARTIN	MMO-063-00	See W-33 Worksheet	1	1,020.60
MSWYB	AC	MANUAL SCAN WHERE YOU BAND II, WINDOWS BASED	MMO-095-14 MMO-056-15	See W-602 Worksheet	6	1,159.14
PARS	AB	PHASE II POSTAL AUTOMATED REDIRECTION SYSTEM PDC-DU	MMO-025-10	See W-34 Worksheet	1	608.55
RCR	AC	REMOTE CHARACTER READER, ENHANCED, MODIFIED	MMO-107-16	See W-344 Worksheet	1	44.52
SPSS	BA	SMALL PARCEL SORTING SYSTEM PHASE2	MMO-115-17	see W-156 Worksheet	1	2,142.42
TACS	AA	TIME AND ATTENDANCE COLLECTION SYSTEM	MMO-077-08 MMO-088-14	See W-61 Worksheet	1	600.62
TAGBLSTR	AA	TAG BLASTER DEDICATED UNIT	MMO-146-11	See W-22 Worksheet	2	267.88
TT	BA	TRAY TRANSPORT POWER ROLLER	MMO-077-10	See W-181 Worksheet	1	604.00
TT	BA	TRAY TRANSPORT POWER ROLLER	MMO-082-10	See W-181 Worksheet	1	28.76
VFS	AA	VENTILATION FILTRATION SYSTEM FOR AFCS	MMO-135-06	See W-11 Worksheet	5	360.85
VFS	BA	VENTILATION FILTRATION FOR 010 SYSTEM	MMO-007-07	See W-12 Worksheet	2	175.32

Total: **87459.93**

SEATTLE NDC

Acronym	Qty	Equipment Description / Justification	MM5/MM6 HOURS	MM-7 HOURS	MPE-9 HOURS	ET-10 HOURS	Total Hours
ATLAS	6	A KIOSK ACE PC THAT COMMUNICATES WITH LOCAL NGTC SERVER ATLAS APPLICATION. AUTOMA	0	0.0	0.00	0.00	0.00
BCR	34	PM FOR BATTERY CHARGERS	0	0.0	68.00	0.00	68.00
FACS	2	FLATS AUTOMATED CULLER SYSTEM.	0	390.6	1472.00	0.00	1862.60
IDUCT	24	SHAKER TABLE PM	0	0.0	388.80	0.00	388.80
MSA	2	MANUAL SORT ASSIST - SORT TO LIGHT	0	0.0	0.00	0.00	0.00
SPARE	1	LOADING SOFTWARE ON ALL CPU BACKUP FOR ALL MPE EQUIPMENT.	0	0.0	0.00	26.00	26.00
USS	1	CLASS CODE AA UNIVERSAL SORT SYSTEM - ACT	0	75.0	1581.00	50.00	1706.00
WRAP	7	PM FOR WRAPPING ROBOTS AND CORRECTIVE MAINTENANCE	0	636.0	0.00	0.00	636.01
		Total	0	1101.61	3509.80	76.00	4687.41

Chapter 4 – MS-1/Building-side Staffing Package

BRIEF AND RECENT HISTORY ON THE MS-1 HANDBOOK

On September 13, 2017, Arbitrator Stephen B. Goldberg ruled in the USPS's favor regarding their changes to the TL-4 (Transmittal Letter) MS-1 Handbook, Operation and Maintenance of Real Property. Part of that ruling was that the Postal Service did not violate Article 19 in increasing local management's discretion to customize MS-1 preventive maintenance times and frequencies. This is important for a couple of reasons:

1. It gave local maintenance management increased discretion when creating their MS-1 staffing packages.

2. Area management had regularly rejected locally created/proposed MS-1 staffing packages.

On August 8, 2019, a national agreement was reached implementing the TL-6 MS-1 Handbook. Among other things:

1. The parties agreed that the TL-5 MS-1 Handbook was never published.

2. It mandates that the employees who have been historically performing the building-side maintenance work in stations and branches shall continue performing that work until adjustments occur resulting from attrition. When attrition in the installation results in a staffing level below the authorized complement, management may determine the occupational group of the employee(s) that will continue to perform the building-side work in the stations and branches.

STEP-1: IDENTIFYING THE APPROVAL DATE OF THE MS-1 STAFFING PACKAGE

As just explained, the TL-6 MS-1 Handbook took effect on August 8, 2019. Once the current/approved MS-1 staffing package is furnished, identify the approval date. If the approval date is prior to August 8, 2019 RFI a copy of the last approved TL-4 MS-1 staffing package, if not already available.

STEP-2: VERIFYING THE ACCURACY OF THE MS-1/BUILDING-SIDE INVENTORY

If the current, approved MS-1 staffing package is dated on or after August 8, 2019, verify the inventory accuracy. This is probably the most challenging task in the Article 12 investigation process due to common lack of familiarity with MS-1 equipment. If that is the case, it is recommended to recruit the help of a knowledgeable BEM to go through the inventory and ensure that all items are listed.

STEP-3: CHALLENGING AREA MANAGEMENT'S REJECTIONS OF PROPOSED STAFFING

As stated, Arbitrator Goldberg agreed with the Postal Service that local management must have increased discretion in creating local MS-1 staffing packages. The MS-1 *Site Staffing History* document identifies:

1. The name of the local postal official that submitted the proposed package.

2. The date that the locally created, proposed package was submitted for approval.

3. Which Area manager rejected the locally created, proposed package.

4. The date that the Area manager rejected the locally created, proposed package.

Once it is known who submitted the locally created, proposed MS-1 staffing packages (and all the dates that they were submitted and resubmitted after being rejected by Area management), RFIs must be submitted for copies of all of the locally created, proposed MS-1 staffing packages that were rejected.

When these are provided, they must be reviewed. Identify what was flagged and the cause for the rejection. It is critical to interview the local postal official who created and recreated the proposed MS-1 staffing packages and get their insight as to what happened, what needed changing and why it was repeatedly rejected. Information requests for related emails must be submitted as well.

STEP-4: INVESTIGATING MANUFACTURER'S RECOMMENDED MAINTENANCE TIMES

Part of the MS-1 inventory will include a list of site-specific equipment that have no predetermined annual staffing hours. These hours must therefore be what the manufacturer recommends.

Through management interviews, determine how local management arrived at the annual staffing hours for the equipment in this inventory. These numbers have been known to be random and arbitrary. Ideally, the manufacturer handbooks are stored within the installation and the staffing hours verified. If these handbooks are not on site, they are typically available online or by contacting the manufacturer.

SAMPLE SITE STAFFING HISTORY AND MS-1 STAFFING DOCUMENTS

This guide includes samples of an MS-1 *Site Staffing History* document and MS-1 staffing package documents. MS-1 staffing package documents include the following PS Forms:

- 4893 – Annual Building Equipment Operational and PM Maint. Workhour Summary

- 4893B – Annual Building Equipment Override and Supplemental Justification
- 4894 – Annual Standard Requirement Building Operational Maintenance
- 4895 – Annual Workhour Requirement for Central Chill Water Plant Op. Maint.
- 4896 – Annual Supplemental Requirement for Building Preventive Maintenance
- 4896A – Annual Standard Requirement Building Preventive Maintenance

MAINTENANCE TECHNICAL SUPPORT CENTER
HEADQUARTERS MAINTENANCE OPERATIONS
UNITED STATES POSTAL SERVICE

Maintenance Management Order

SUBJECT: Guidelines for Creating Detailed Local Building and Building Equipment Maintenance Preventive Maintenance Checklists

DATE: February 22, 2022

TO: All Maintenance Sites

PUB NO: MMO-057-21
FILE CODE: M
FILE ID: mm21056
REV LEVEL: ah

Online Change Record		
Change #	**Date**	**Description of Change**
1	3/18/2022	Att. 1, Table 1-1, line item 166, guide corrected to HVAC-3.

This Maintenance Management Order (MMO) **supersedes MMO-007-20** and provides local maintenance managers with guidelines to develop detailed Building and Building Equipment Maintenance Preventive Maintenance (PM) checklists. Attachment 1 provides a table listing equipment and corresponding PM guidelines. Attachment 2 provides the PM guides. Attachment 3 provides sample USPS building equipment annual staffing workhour requirement forms. This bulletin applies to Acronym ADMIN, Class Code AA.

The PM requirements and tasks in Attachment 2 provide the minimum required PM and frequencies that should be modified as necessary based on manufacturer's requirements, local conditions, usage, or local ordinances. Manufacturer recommendations may be considered with justification as they relate to Occupational Safety and Health Administration (OSHA), federal, state, and local regulations. Ensure all required OSHA safety requirements including but not limited to Personal Protective Equipment (PPE), Electrical Work Program (EWP), local Energy Control Procedures (ECP), and Safety Data Sheet (SDS) are added to the locally developed PM checklists.

The development of a facility Building and Building Equipment Maintenance (BEM) Plan depends on a complete and accurate inventory. All building equipment that is to be maintained must be identified and listed in the site staffing software application. Failure to accurately inventory the facility equipment may result in inadequate support resources. The site staffing projection for building equipment maintenance is derived and calculated within the staffing software application and is based on the building equipment inventory, maintenance standards, and frequencies. Each inventory item in the staffing software application earns an annual work hour allowance, which should not be exceeded without proper documentation and justification.

Station/Branch and Associate Office building equipment entered into the staffing software application does not count toward building equipment maintenance staffing hours because those facilities are maintained by Field Maintenance and associated staffing hours are calculated in a separate section of the staffing software application.

Other equipment or building systems supported by contract or other means, must be listed, but designated as “maintained by contract”.

Route scheduling within eMARS should be coordinated to allow inspection of numerous smaller simplistic components at the same time to minimize travel within the facility. For example: Perform the inspections of steam traps, chilled water valves, other miscellaneous Heating, Ventilation, and Air Conditioning (HVAC) valves and air handler units at the same time when feasible.

For questions or comments concerning this bulletin, contact HQ Maintenance Operations at _HQMaintenanceOperations@usps.gov.



Thomas Rabicki
Executive Manager
Maintenance Policy, Programs, and Support
HQ Maintenance Operations

Attachments:
1. Equipment Inventory Reference Table
2. Building and Building Equipment Preventive Maintenance Guides
3. USPS Building Equipment Annual Staffing Workhour Requirement Forms

ATTACHMENT 1

EQUIPMENT INVENTORY REFERENCE TABLE

1.0 EQUIPMENT INVENTORY TABLE

Table 1-1. Equipment Inventory Reference Table

Line	Item	eMARS Equip. Description	eMARS Acronym	Class Code	PM Guide No(s)
1	AGV	AGV Seegrid Pallet Jack	AGV	SP	MMO*
2	AGV	AGV Seegrid Tow Motor	AGV	ST	MMO*
3	AGV	AGV Seegrid Server System	AGV	SZ	MMO*
4	AGV	AGV Daifuku Pallet Jack	AGV	UP	MMO*
5	AGV	AGV Daifuku Tow Motor	AGV	UT	MMO*
6	AGV	AGV Daifuku Server System	AGV	UZ	NONE**
7	AGV	Automated Guided Vehicles Mission Assignment Sys	AGVM	AA	NONE**
8	Air Curtain	Air Curtain	FAN	AC	NONE**
9	Air Compressors	Compressed Air HVAC	AIR (1)	BA	MISC-1
10	Air Compressors	Compressed Air Mechanization/Automation	AIR	AA	MISC-1
11	Air Compressors	Compressed Air Other	AIR	ZZ	MISC-1
12	Air-Conditioning Machine Package Unit <10 Tons	Rooftop Or Package Cooling Only	HVACPKG	AA	HVAC-1, HVAC-15
13	Air-Conditioning Machine Package Unit >10 Tons And <=30 Tons	Rooftop Or Package Cooling Only	HVACPKG	AA	HVAC-1, HVAC-15
14	Air-Conditioning, Window Units	AC Window Units	HVACPKG	BB	HVAC-2, HVAC-15
15	Air Dryer	Compressed Air Dryer	AIR	CA	NONE**

Line	Item	eMARS Equip. Description	eMARS Acronym	Class Code	PM Guide No(s)
16	Air Handling Unit-Other <=10hp	Air Handling Unit-Other <=10hp	AHU	EA	HVAC-4, HVAC-13, HVAC-15
17	Air Handling Unit-Other >10hp	Air Handling Unit-Other >10hp	AHU	EB	HVAC-4, HVAC-13, HVAC-16
18	Boilers, Cast Iron And Steel	Boiler Low Press, Hot Water, Gas Fired	BOILER	AA	HVAC-6,
19	Boilers, Cast Iron And Steel	Boiler Low Press, Hot Water, Oil Fired	BOILER	BA	HVAC-5, HVAC-6,
20	Boilers, Cast Iron And Steel	Boiler Low Press, Hot Water, Elect Fire	BOILER	CA	HVAC-6,
21	Boilers, Cast Iron And Steel	Boiler High Press, Hot Water, Gas Fired	BOILER	DA	HVAC-6,
22	Boilers, Cast Iron And Steel	Boiler High Press, Hot Water, Oil Fired	BOILER	EA	HVAC-5, HVAC-6,
23	Boilers, Cast Iron And Steel	Boiler High Press, Hot Water, Elect	BOILER	FA	HVAC-6,
24	Boilers, Cast Iron And Steel	Boiler Low Press, Steam, Gas Fired	BOILER	GA	HVAC-6,
25	Boilers, Cast Iron And Steel	Boiler Low Press, Steam, Oil Fired	BOILER	HA	HVAC-5, HVAC-6,
26	Boilers, Cast Iron And Steel	Boiler Low Press, Steam, Elect Fired	BOILER	IA	HVAC-6,
27	Boilers, Cast Iron And Steel	Boiler High Press, Steam, Gas Fired	BOILER	JA	HVAC-6,
28	Boilers, Cast Iron And Steel	Boiler High Press, Steam, Oil Fired	BOILER	KA	HVAC-5, HVAC-6,
29	Boilers, Cast Iron And Steel	Boiler High Press, Steam, Elect Fired	BOILER	LA	HVAC-6,
30	Burner, Gas	Burner Boiler (Gas)	BURNER	AG	HVAC-7
31	Burner, Oil	Burner Boiler (Oil)	BURNER	AO	HVAC-8
32	Coils, Preheat, Reheat, Etc. (At Remote Locations)	Coils Preheat Reheat Etc. (Remote Locations)	HVACO	CA	HVAC-9
33	Compactor PTR	Compactor PTR	COMPACT	BA	MMO*
34	Condensers, Air Cooled	Air Cooled Condensers <10 Tons	COOL	HA	HVAC-3, ELEC-1
35	Condensers, Air Cooled	Air Cooled Condensers >10 Tons And <=30 Tons	COOL	HB	HVAC-3, ELEC-1

Line	Item	eMARS Equip. Description	eMARS Acronym	Class Code	PM Guide No(s)
36	Condensers, Air Cooled	Air Cooled Condensers >30 Tons	COOL	HC	HVAC-3, ELEC-1
37	Condensers, Evaporative	Condenser, Evaporative	COOL	GA	PLUM-7, ELEC-1
38	Cooling Towers	Cooling Equipment Cooling Towers	COOL	FA	HVAC-11.1, HVAC-11.2, HVAC-12, ELEC-1
39	Docks- All Related Equipment	Docks- All Related Equipment	DOCKS	AA	NONE**
40	Dock Levelers, Manual	Dock Loading Ramp Adjustable (Manual)	DOCKS	AB	MISC-16
41	Dock Levelers, Powered	Dock Levelers - Loading Ramps (Powered)	DOCKS	AC	MISC-8
42	Dock (Powered Lift)	Dock (Powered Lift)	DOCKS	AD	NONE**
43	Dock Boards Fixed	Dock Boards Fixed	DOCKS	AE	NONE**
44	Dock Lights (Trailer)	Dock Lights (Trailer)	DOCKS	AF	NONE**
45	Dock Scissor Lift	Dock Scissor Lift	DOCKS	AI	NONE**
46	Doors, Pedestrian, Main Entrance And Dock Entrance, (Power Operated)	Doors Main Entrance Power Operated	DOOR	AP	MISC-6
47	Doors, Pedestrian, Main Entrance And Dock Entrance, (Power Operated)	Turnstile Power Operated	DOOR	AT	MISC-6
48	Doors, Pedestrian, Main Entrance And Dock Entrance (Non-Powered)	Doors Main Entrance (Non-Powered)	DOOR	AM	MISC-7
49	Doors, Dock, Powered Operated	Dock Door (Trailer Loading And Unloading)	DOCKS	AP	MISC-5-1
50	Doors, Dock Manually Operated	Dock Door (Trailer Loading And Unloading)	DOCKS	AM	MISC 5.2
51	Door High Speed	Door High Speed	DOOR	HS	NONE**
52	Drinking Water Coolers	Drinking Water Coolers	PLUMB	DW	PLUM-13

Line	Item	eMARS Equip. Description	eMARS Acronym	Class Code	PM Guide No(s)
53	Dust Collection System	Dust Collection System	DUST	AA	NONE**
54	Elevator Electric, Automatic	Elevator Electric, Automatic	EL	AA	NONE**
55	Elevator Electric, Manual	Elevator Electric, Manual	EL	BA	NONE**
56	Elevator Hydraulic, Automatic	Elevator Hydraulic, Automatic	EL	CA	NONE**
57	Elevator Hydraulic, Manual	Elevator Hydraulic, Manual	EL	DA	NONE**
58	Elevator Escalator	Elevator Escalator	EL	EA	NONE**
59	Electrical Power Supply 15KV And Above	Electrical Power Supply 15KV And Above	ELEC	PA	NONE**
60	Electrical Power Supply Below 7 KV	Electrical Power Supply Below 7 KV	ELEC	PB	NONE**
61	Electrical Panel Control	Electrical Panel Control	ELEC	PC	NONE**
62	Electrical Panel Distribution	Electrical Panel Distribution	ELEC	PD	ELEC-5
63	Electrical Power Supply 7 - 14 KV	Electrical Power Supply 7 - 14 KV	ELEC	PS	NONE**
64	Emergency Systems Emergency Lighting	Emergency Systems Emergency Lighting	EMSYS	EL	NONE**
65	Emergency Shower	Emergency Showers	EMSYS	ES	EMSYS MMO, PLUM-15
66	Eyewash, Plumbed	Emergency Systems Eyewash	EMSYS	PW	EMSYS MMO, PLUM-14
67	Eyewash, Self-Contained	Emergency Systems Eyewash	EMSYS	SW	EMSYS MMO, PS FORM 4894
68	Emergency Exit Signs	Emergency Exit Signs	EMSYS	EX	EMSYS MMO, PS FORM 4894
69	Emergency Systems Fire Alarm	Emergency Systems Fire Alarm	EMSYS	FA	EMSYS MMO
70	Fans, Centrifugal (Exhaust Or Return Air)	Fan Centrifugal	FAN	FC	HVAC-12
71	Fans, Propeller, Pedestal Or Wall-Mounted	Fan Propeller	FAN	FP	HVAC-16

Line	Item	eMARS Equip. Description	eMARS Acronym	Class Code	PM Guide No(s)
72	Fans Propeller >=24 Inches	Fans Propeller >=24 Inches	FAN	FQ	NONE**, 4894
73	Filters, Roll Type, Disposable Media	Filters Roll Type Disposable Media	FILTER	FR	HVAC-13
74	Controls And Mechanisms For Roll-Type Filters	Controls And Mechanisms For Roll-Type Filters	HVACINS	CA	HVAC-14
75	Filters, Throw Away	Filters Throw Away	FILTER	FT	HVAC-15
76	Fire Dampers (In Duct)	Fire Damper All	EMSYS	FD	HVAC-24
77	Fire Doors - Sliding Type	Fire Doors - Sliding Type	DOOR	FD	MISC-10
78	Fire Doors - Swinging Type, Stairwells And Exit Ways	Fire Door Stairwells And Exitways (Swinging)	DOOR	FS	MISC-9
79	Fire Extinguisher	Emergency Systems Fire Extinguishing	EMSYS	FE	EMSYS MMO, PLUM-1
80	Fire Pumps, Electric Motor Drive	Fire Pump, Electric Motor Drive	PLUMB	FE	PLUM-11, EMS-8
81	Fire Pumps, Internal Combustion Engine Drive	Fire Pump, Internal Combustion Engine Drive	PLUMB	FG	PLUM-12, EMS-8
82	Furnace Forced Air Gas Fired	Furnace Forced Air Gas Fired	FURNACE	AA	MS-24
83	Furnace Forced Air Oil Fired	Furnace Forced Air Oil Fired	FURNACE	BA	NONE**
84	Furnace Forced Air Elect Fired	Furnace Forced Air Elect Fired	FURNACE	CA	NONE**
85	Furnace Forced Air Gas Split System	Furnace Forced Air Gas Split System	FURNACE	DA	NONE**
86	Furnace Forced Air Oil Split System	Furnace Forced Air Oil Split System	FURNACE	EA	NONE**
87	Furnace Forced Air Elect Split System	Furnace Forced Air Elect Split System	FURNACE	FA	NONE**
88	Fusible Link Smoke Vents (Roof)	Fusible Link Smoke Vents (Roof)	BLDG	SV	NONE**
89	Generators, Emergency, Gasoline Or Natural Gas Engines	Fixed Mount Permanent Generator	GEN	BA	ELEC-2, ELEC-4, EMS-5
90	Generators, Emergency, Fixed Diesel	Generator Diesel (Fixed)	GEN	BB	ELEC-3, ELEC-4, EMS-5

Line	Item	eMARS Equip. Description	eMARS Acronym	Class Code	PM Guide No(s)
91	Generators, Contingency	Portable Generator Less Than And Including 15KW	GEN	AA	MMO*
92	Generators, Contingency	Portable Generator Greater Than 15KW	GEN	AB	MMO*
93	Generators, Contingency	Generator Other (Portable)	GEN	AC	MMO*
94	Grease Traps	Grease Traps	PLUMB	GT	MMO*
95	Ground Fault Circuit Interrupter (GFCI)	Ground Fault Circuit Interrupter (GFCI) Electrical Receptacle	ELEC	GF	EMSYS MMO, PS FORM 4894
96	Building Automation System (BAS)	GMS Building Automation System	GMS	BA	NONE**
97	Heaters, Baseboard, Electric	Heater Electric Baseboard - 706	HVACO	EA	HVAC-21
98	Heaters, In Duct, Electric	Heater Electric In Duct	HVACO	DA	HVAC-20
99	Heaters, Unit, Gas-Fired	Heater	HVACO	AA	HVAC-23
100	Heaters, Unit, Steam Or Hot Water	Heater	HVACO	AA	HVAC-22
101	Heating Only, Package Unit	Rooftop Heating Only, Gas Fired	HVACPKG	BA	NONE**
102	Heating Only, Package Unit	Rooftop Heating Only, Oil Fired	HVACPKG	CA	NONE**
103	Heating Only, Package Unit	Rooftop Heating Only, Elect Fired	HVACPKG	DA	NONE**
104	Heating/Cooling Units, Package Unit	Rooftop Or Package Heating Cooling, Gas Fired	HVACPKG	EA	HVAC-17
105	Heating/Cooling Units, Package Unit	Rooftop Or Package Heating Cooling, Oil Fired	HVACPKG	FA	HVAC-17
106	Heating/Cooling Units, Package Unit	Rooftop Or Package Heating Cooling, Elect Fired	HVACPKG	GA	PLUM-9, ELEC-1, PLUM-7
107	Heat Pump	Heat Pump Air Source - No Backup	HTPUMP	AA	NONE**
108	Heat Pump	Heat Pump Air Source - Gas Backup	HTPUMP	AB	NONE**
109	Heat Pump	Heat Pump Air Source - Oil Backup	HTPUMP	AC	NONE**
110	Heat Pump	Heat Pump Air	HTPUMP	AD	NONE**

Line	Item	eMARS Equip. Description	eMARS Acronym	Class Code	PM Guide No(s)
		Source - Elec Backup			
111	Heat Pump	Heat Pump Gnd Source Clsed Loop No Bkup	HTPUMP	BA	NONE**
112	Heat Pump	Heat Pump Gnd Source Clsed Loop Gas Bku	HTPUMP	BB	NONE**
113	Heat Pump	Heat Pump Gnd Source Clsed Loop Oil Bku	HTPUMP	BC	NONE**
114	Heat Pump	Heat Pump Gnd So. Closed Loop Elec Bkup	HTPUMP	BD	NONE**
115	Heat Pump	Heat Pump Gnd Source Aquifer No Bkup	HTPUMP	CA	NONE**
116	Heat Pump	Heat Pump Gnd Source Aquifer Gas Bkup	HTPUMP	CB	NONE**
117	Heat Pump	Heat Pump Gnd Source Aquifer Oil Bkup	HTPUMP	CC	NONE**
118	Heat Pump	Heat Pump Gnd Source Aquifer Elec Bkup	HTPUMP	CD	NONE**
119	Hoist	Trolley Mounted Hoist	HOIST	AA	MMO*
120	Hoist	Mobile Boom Style Hoist	HOIST	BA	MMO*
121	Hoist	Other Manual Hoist	HOIST	DA	MMO*
122	Hot Water Heaters, Converters (Industrial)	Hot Water Heater Converters Industrial	PLUMB	AA	PLUM-9, ELEC-1, PLUM-7
123	Hot Water Heaters Commercial Type	Hot Water Heaters Commercial Type	PLUMB	WC	PLUM-10, ELEC-1, PLUM-7
124	Hot Water Heaters, Domestic Type	Hot Water Heater (Domestic) - Electric	PLUMB	WC	PLUM-10, ELEC-1, PLUM-7
125	Hot Water Heaters, Domestic Type (Gas Or Oil Fired)	Hot Water Heater (Domestic) - Oil Gas	PLUMB	WG	PLUM-10, ELEC-1, PLUM-7

Line	Item	eMARS Equip. Description	eMARS Acronym	Class Code	PM Guide No(s)
126	Humidifier	Humidification System	HUMID	AA	NONE**
127	Dehumidifier	Dehumidifier	HUMID	BA	NONE**
128	Lawnmowers And Edgers (Gasoline Powered)	Bldg, Outside Equipment	BLDG	BA	MISC-2
129	Lead Acid PIV Battery	Battery	BATTERY	AA	MISC-19
130	Magnetic Locking System	Magnetic Locking System	DOOR	ML	NONE**
131	MOPE	Mobile Op Eq, Forklift, Ride Or Walk, Motorized	MOPE	AA	MMO*
132	MOPE	Toyota Forklift Model 5	MOPE	AB	MMO*
133	MOPE	Toyota Forklift Model 6	MOPE	AC	MMO*
134	MOPE	Toyota Forklift Model 7	MOPE	AD	MMO*
135	MOPE	Toyota Forklift Model 8	MOPE	AE	MMO*
136	MOPE	Clark Forklift (All Models)	MOPE	AL	MMO*
137	MOPE	Crown Forklift (All Models)	MOPE	AM	MMO*
138	MOPE	Hyster Forklift (All Models)	MOPE	AN	MMO*
139	MOPE	Yale Forklift (All Models)	MOPE	AO	MMO*
140	MOPE	Mobile Op Eq Tow Tractor Tugger Power Ox	MOPE	BA	MMO*
141	MOPE	Toyota Tow Tractor (All DC Models)	MOPE	BB	MMO*
142	MOPE	Toyota Tow Tractor (All AC Models)	MOPE	BC	MMO*
143	MOPE	Taylor Dunn (All Models)	MOPE	BD	MMO*
144	MOPE	Mobile Op Eq Pallet Truck Motorized - Non Motorized	MOPE	CA	MMO*
145	MOPE	Toyota Riding Pallet Truck (All Models)	MOPE	CB	MMO*

Line	Item	eMARS Equip. Description	eMARS Acronym	Class Code	PM Guide No(s)
146	MOPE	Toyota Walking Pallet Truck (All Models)	MOPE	CC	MMO*
147	MOPE	Crown Pallet Truck (All Models)	MOPE	CD	MMO*
148	MOPE	Mobile Op Eq-Other	MOPE	DA	MMO*
149	MOPE	Mobile Op Eq-Mini Lift FSS Only	MOPE	EA	MMO*
150	Motors, Over 5hp	Motor Electric Over 5 HP	ELEC	MT	ELEC-1
151	Paper Baler	Baler	BALER	AA	MISC-4
152	PIVMS	PIVMS	PIVMS	AA	MMO*
153	Pump, Centrifugal	Pumps, Centrifugal (Not Integral With Motor)	PLUMB	PC	PLUM-7, ELEC-1
154	Pump Chiller Water	Pump Chiller Water	PLUMB	PC	NONE**, PLUM-7, ELEC-1
155	Pump Condenser Water	Pump Condenser Water	PLUMB	PC	NONE**, PLUM-7, ELEC-1
156	Pump Hot Water	Pump Hot Water	PLUMB	PC	NONE**, PLUM-7, ELEC-1
157	Pumps, Sump (Life)	Pump, Sump (Sewage Or Life)	PLUMB	PS	PLUM-2
158	Pumps, Condensate Or Vacuum	Pump, Condensate Or Vacuum	PLUMB	PV	HVAC-10
159	Pump Sewer Ejector	Pump Sewer Ejector	PLUMB	PS	NONE**
160	UPV	Unfired Pres Vessel All Types - Models	UPV	AA	NONE**
161	Refrigeration Machines (Absorption Type)	Absorption Unit Cooling Only	HVACABS	AA	HVAC-18, ELEC-1, PLUM-7
162	Refrigeration Machine (Centrifugal And Reciprocating)	Water In Evap-Water Cool Condenser	COOL	AA	HVAC-19, ELEC-1, PLUM-7

Line	Item	eMARS Equip. Description	eMARS Acronym	Class Code	PM Guide No(s)
163	Roof, Inspection: Roof work should only include periodic visual inspection. Any required roof repairs must to be considered under and coordinated through the national roof contract. Note: (All roof types included)	Roofing Built-Up Roof Drains Etc.	ROOF	AA	PLUM-8
164	Floor Scrubbers, Automatic, Vacuum, Battery Operated	Floor Scrubber	MOPE	FS	MISC-18
165	Snow Blower - Walking Type	Snow Blower - Walking	MOPE	SB	MISC-15
166	Split System (Condenser)	Split System Condenser Unit	COOL	SA	HVAC-3
167	Split System (Evaporator)	Split System Evaporator Unit	COOL	SB	HVAC-25 , HVAC-26
168	Split System (Evaporator)	Split System Evaporator Unit With Electric Heat	COOL	SE	HVAC-25 , HVAC-26
169	Split System (Evaporator)	Split System Evaporator Unit With Gas Heat	COOL	SG	HVAC-25 , HVAC-26
170	Split System (Evaporator)	Split System Evaporator Unit With Oil Heat	COOL	SO	HVAC-25 , HVAC-26
171	Split System (Evaporator And Condenser)	Split System Evaporator Unit With Other Heat	COOL	SZ	HVAC-25 , HVAC-26
172	Sprinkler Head (Sprinkled Areas)	Fire Suppression System	EMSYS	FS	EMSYS MMO
173	Stationary Packers	Compactor	COMPACT	AA	MISC-11, MISC-12, MISC-13
174	Sweepers Electric (Battery)	Sweeper Electric	MOPE	SE	MISC-17
175	Sweepers (Gasoline Powered)	Sweeper Gas	MOPE	SG	MISC-3
176	Tanks	Storage Tank Diesel Fuel	TANKS	CA	NONE**

Line	Item	eMARS Equip. Description	eMARS Acronym	Class Code	PM Guide No(s)
177	Tanks	Storage Tank Waste Fuel	TANKS	DA	NONE**
178	Tanks	Storage Tank Waste Solvent	TANKS	KA	NONE**
179	Tanks	Storage Tank Engine Oil	TANKS	JA	NONE**
180	Tanks	Storage Tank Other	TANKS	NA	NONE**
181	Trailer Restraints	Trailer Restraint	DOCKS	AH	MISC-20, MISC-21
182	Transformer	Transformer	ELEC	TR	NONE**
183	Transformer Switch	Transformer Switch	ELEC	TS	NONE**
184	Transformer Vault	Transformer Vault	ELEC	TV	NONE**
185	Traps, Steam (All Types)	Steam Trap, All Types	BOILER	ST	PLUM-6
186	Valves, Manually Operated (Mainline Or Critical - Over 2 In)	Valve, Manually Operated Mainline Or Critical Over 2-in.	PLUMB	VC	PLUM-4
187	Valve, Fire Control	Fire Suppression System	EMSYS	FS	EMSYS MMO
188	Valves, Motor Operated	Valve, Motor Operated	PLUMB	VM	PLUM-5
189	Valves, Regulating (Steam)	Valve, Regulating (Steam)	PLUMB	VR	PLUM-3
190	VFD	Variable Frequency Drive	ELEC	VF	NONE**
191	VAV	Variable Air Volume Unit	HVACVAV	AA	NONE**

*MMO: refer to appropriate MMO for task.

**NONE: no guides apply.

5. Include Unfired Pressure Vessel (UPV), if applicable.

6. Use acronym for equipment or system on which this item is installed.

When creating an Equipment Record in the eMARS Equipment Module, the Site will generate one record for each piece or type of equipment depending on the specific equipment.

ATTACHMENT 3

USPS BUILDING EQUIPMENT ANNUAL STAFFING

WORKHOUR REQUIREMENT FORMS

1.0 STAFFING WORKHOUR REQUIREMENT FORMS

The following forms are output from the entries made in the staffing software application.

- PS Form 4893 – Annual Building Equipment Operational and Preventive Maintenance Workhour Summary (Figure 3-1)
- PS Form 4893B – Annual Building Equipment Override and Supplemental Maintenance Justification (Figure 3-2)
- PS Form 4894, Page 1 of 2 – Annual Standard Requirement Building Operational Maintenance (Figure 3-3)
- PS Form 4894, Page 2 of 2 – Annual Standard Requirement Building Operational Maintenance (Figure 3-4)
- PS Form 4895 – Annual Workhour Requirement for Central Chill Water Plant Operational Maintenance (Figure 3-5)
- PS Form 4896, Page 1 of 2 – Annual Supplemental Requirement for Building Preventive and Operational Maintenance (Figure 3-6)
- PS Form 4896, Page 2 of 2 – Annual Supplemental Requirement for Building Preventive and Operational Maintenance (Figure 3-7)
- PS Form 4896A, Page 1 of 6 – Annual Standard Requirement Building Preventive Maintenance (Figure 3-8)
- PS Form 4896A, Page 2 of 6 – Annual Standard Requirement Building Preventive Maintenance (Figure 3-9)
- PS Form 4896A, Page 3 of 6 – Annual Standard Requirement Building Preventive Maintenance (Figure 3-10)
- PS Form 4896A, Page 4 of 6 – Annual Standard Requirement Building Preventive Maintenance (Figure 3-11)

FOR REVIEW PURPOSES - BLANK FORM

U.S. POSTAL SERVICE ANNUAL BUILDING EQUIPMENT OPERATIONAL AND PREVENTIVE MAINTENANCE WORKHOUR SUMMARY	BUILDING(s):	GROSS INTERIOR SQFT:	SPRINKLERS SQFT:	DATE: PREPARED BY:

LINE NO.	WORK DESCRIPTION	PREVENTIVE MAINTENANCE		OPERATIONAL MAINTENANCE			CORRECTIVE/MISC MAINTENANCE	TOTAL ANNUAL WORKHOURS
		4896A	4896	4894	4895	4896		
A	B	C	D	E	F	G	H	I
1	HVAC							
2	ELEC							
3	PLUM							
4	EMS							
5	MISC							
6	SUBTOTALS							
7	CORRECTIVE	*	*				**	
8	MISCELLANEOUS						†	
	TOTAL WORKHOURS							
	TOTAL FTE							

* 8% of the Subtotal
** 8 Hours per 1000 Gross Interior SQFT
† 0.1 Hours per 1000 SQFT (Sprinkler SQFT)

PS FORM 12/28/2018 **4893 - BLANK FORM**

Figure 3-1. PS Form 4893 – Annual Building Equipment Operational and Preventive Maintenance Workhour Summary

FOR REVIEW PURPOSES - BLANK FORM

U.S. POSTAL SERVICE ANNUAL BUILDING EQUIPMENT OVERRIDE AND SUPPLEMENTAL MAINTENANCE JUSTIFICATION		BUILDING(s):	DATE: PREPARED BY:

TABLE A: OPERATIONAL MAINTENANCE				
GUIDE CAT/NO	TASK DESCRIPTION	EQUIPMENT TYPE	EQUIPMENT DESCRIPTION	JUSTIFICATION
OVERRIDE TASKS				
*				
*				
*				
*				
*				
SUPPLEMENTAL TASKS				
*				
*				
*				
*				
*				

TABLE B: PREVENTIVE MAINTENANCE				
GUIDE CAT/NO	TASK DESCRIPTION	EQUIPMENT TYPE	EQUIPMENT DESCRIPTION	JUSTIFICATION
OVERRIDE TASKS				
*				
*				
*				
*				
*				
SUPPLEMENTAL TASKS				
*				
*				
*				
*				
*				

PS FORM 12/28/2018 **4893B - BLANK FORM**

Figure 3-2. PS Form 4893B – Annual Building Equipment Override and Supplemental Maintenance Justification

FOR REVIEW PURPOSES - BLANK FORM

U.S. POSTAL SERVICE ANNUAL STANDARD REQUIREMENT BUILDING OPERATIONAL MAINTENANCE		BUILDING(s):	DATE: PREPARED BY:

TABLE A: HVAC

GUIDE NO	TASK DESCRIPTION	QUANTITY	FREQUENCY	WORK HOURS (per freq)	ANNUAL TRAVEL TIME	TOTAL ANNUAL WORKHOURS
HVAC-12	FANS CENTRIFUGAL >15HP		12	0.03		
NONE	FANS PROPELLER >=24INCHES		12	0.03		
SUBTOTAL						

TABLE B: ELEC

GUIDE NO	TASK DESCRIPTION	QUANTITY	FREQUENCY	WORK HOURS (per freq)	ANNUAL TRAVEL TIME	TOTAL ANNUAL WORKHOURS
NONE	BATTERY SYSTEM, 24 VOLT		1	0.08		
NONE	BATTERY SYSTEM, 48 VOLT		1	0.16		
NONE	BATTERY SYSTEM, 120 VOLT		1	0.33		
EMS-11	GROUND FAULT CIRCUIT INTERRUPTER (GFCI)		2	0.02		
NOGUIDE1	MAIN ELECTRICAL CUBICLE/SWITCHGEAR ROOMS (>600VAC)		52	0.08		
NOGUIDE2	SWITCHBOARD ROOMS (<600VAC)		52	0.05		
NOGUIDE3	TRANSFORMER VAULTS		52	0.06		
SUBTOTAL						

TABLE C: PLUM

GUIDE NO	TASK DESCRIPTION	QUANTITY	FREQUENCY	WORK HOURS (per freq)	ANNUAL TRAVEL TIME	TOTAL ANNUAL WORKHOURS
NOGUIDE4	HYDRO-PNEUMATIC SYSTEM (INCL FIRE PROTECTION SYSTEM)			0.08		
NONE	PRESSURE REDUCING AND REGULATING STATIONS - STEAM AND WATER		1	0.02		
NONE	PUMPS >5HP, REMOTE FROM OTHER EQUIPMENT		1	0.03		
NONE	SUMP PUMP, OPERATIONAL		12	0.05		
SUBTOTAL						

TABLE D: EMS

GUIDE NO	TASK DESCRIPTION	QUANTITY	FREQUENCY	WORK HOURS (per freq)	ANNUAL TRAVEL TIME	TOTAL ANNUAL WORKHOURS
EMS-4	EMERGENCY EXIT SIGNS		12	0.02		
EMS-10	EMERGENCY EXIT SIGNS		1	0.02		
EMS-12	EMERGENCY EYEWASH, SELF-CONTAINED		12	0.02		
EMS-1	EMERGENCY EYEWASHES		52	0.10		
EMS-3	EMERGENCY LIGHTS		12	0.02		
EMS-9	EMERGENCY LIGHTS		1	0.02		
EMS-2	EMERGENCY SHOWERS		52	0.10		
EMS-14	FIRE CONTROL VALVE, LOCKED OR SUPERVISED		12	0.10		
EMS-14	FIRE CONTROL VALVE, SEALED		52	0.10		
EMS-7	FIRE EXTINGUISHER, PORTABLE, STORED-PRESSURE		12	0.02		
EMS-8	FIRE PUMPS		52	0.40		
SUBTOTAL						

Figure 3-3. PS Form 4894, Page 1 of 2 – Annual Standard Requirement Building Operational Maintenance

TABLE E: MISC						
GUIDE NO	TASK DESCRIPTION	QUANTITY	FREQUENCY	WORK HOURS (per freq)	ANNUAL TRAVEL TIME	TOTAL ANNUAL WORKHOURS
SUBTOTAL						

PS FORM 12/28/2018 **4894 - BLANK FORM**

Figure 3-4. PS Form 4894, Page 2 of 2 – Annual Standard Requirement Building Operational Maintenance

FOR REVIEW PURPOSES - BLANK FORM

U.S. POSTAL SERVICE ANNUAL WORKHOUR REQUIREMENT FOR CENTRAL CHILL WATER PLANT OPERATIONAL MAINTENANCE		BUILDING(s):	DATE: PREPARED BY:

BUILDING				
LINE NO.	EQUIPMENT DESCRIPTION	OPERATING DAYS	WORKHOURS (per day)	ANNUAL WORKHOURS
1			0.5	
2	SUBTOTAL			
3	BUILDING CHILLER OPERATING DAYS		0.5	
	TOTAL WORKHOURS *			

* Operational Checks are limited to one hour per operating day for the first chiller. All additional chillers are workloaded at 0.5 hours per operating day.

PS FORM 12/28/2018 **4895 - BLANK FORM**

Figure 3-5. PS Form 4895 – Annual Workhour Requirement for Central Chill Water Plant Operational Maintenance

FOR REVIEW PURPOSES - BLANK FORM

U.S. POSTAL SERVICE ANNUAL SUPPLEMENTAL REQUIREMENT FOR BUILDING PREVENTIVE AND OPERATIONAL MAINTENANCE	BUILDING(s):	DATE: PREPARED BY:

TABLE A: PREVENTIVE MAINTENANCE

GUIDE	TASK DESCRIPTION	EQUIPMENT TYPE	EQUIPMENT DESCRIPTION	FREQUENCY (per year)	WORKHOURS (per freq)	TOTAL WORKHOURS
						0
						0
						0
						0
						0
						0
						0
						0
						0
						0
						0
						0
						0
						0
						0
						0
						0
						0
						0
						0
	SUBTOTAL					0

TABLE B: OPERATIONAL MAINTENANCE

GUIDE	TASK DESCRIPTION	EQUIPMENT TYPE	EQUIPMENT DESCRIPTION	FREQUENCY (per year)	WORKHOURS (per freq)	TOTAL WORKHOURS
						0
						0
						0
						0
						0
						0
						0
						0
						0
						0
						0
						0
						0
						0
						0

Figure 3-6. PS Form 4896, Page 1 of 2 – Annual Supplemental Requirement for Building Preventive and Operational Maintenance

TABLE B: OPERATIONAL MAINTENANCE						
GUIDE	TASK DESCRIPTION	EQUIPMENT TYPE	EQUIPMENT DESCRIPTION	FREQUENCY (per year)	WORKHOURS (per freq)	TOTAL WORKHOURS
						0
						0
						0
						0
						0
	SUBTOTAL					0

PS FORM 12/28/2018 **4896 - BLANK FORM**

Figure 3-7. PS Form 4896, Page 2 of 2 – Annual Supplemental Requirement for Building Preventive and Operational Maintenance

FOR REVIEW PURPOSES - BLANK FORM

U.S. POSTAL SERVICE ANNUAL STANDARD REQUIREMENT BUILDING PREVENTIVE MAINTENANCE		BUILDING(s):	DATE: PREPARED BY:

TABLE A: HVAC

GUIDE NO.	TASK DESCRIPTION	QUANTITY	FREQUENCY (per year)	WORK HOURS (per freq)	TOTAL WORK HOURS
HVAC-1	AC PACKAGE UNIT <10 TONS		1	8.50	
HVAC-1	AC PACKAGE UNIT >=10 TONS		1	10.00	
HVAC-2	AIR-CONDITIONING, WINDOW UNITS		1	0.50	
HVAC-3	AIR COOLED CONDENSERS <= 10 TONS		1	0.75	
HVAC-3	AIR COOLED CONDENSERS >10 TONS and <=30 TONS		1	1.00	
HVAC-3	AIR COOLED CONDENSERS >30 TONS		1	1.75	
HVAC-4	AIR HANDLERS		1	2.50	
HVAC-4	AIR HANDLERS >10HP		1	4.50	
HVAC-5	BOILERS, OIL FIRED		1	10.00	
HVAC-6	BOILERS, CAST-IRON AND STEEL		1	10.00	
HVAC-7	BURNER, GAS		1	5.00	
HVAC-8	BURNER, OIL		1	5.00	
HVAC-9	COILS, PREHEAT, REHEAT, ETC. (REMOTE FROM AIR HANDLER)		1	1.00	
HVAC-10	CONDENSATE OR VACUUM PUMPS (ON STEAM RETURN SYSTEM)		1	2.00	
HVAC-11.1	COOLING TOWERS 501 - 1000 TON SPRING STARTUP (1 CELL)		1	20.30	
HVAC-11.1	COOLING TOWERS 501 - 1000 TON SPRING STARTUP (2 CELLS)		1	40.60	
HVAC-11.1	COOLING TOWERS 501 - 1000 TON SPRING STARTUP (3 CELLS)		1	60.90	
HVAC-11.1	COOLING TOWERS 501 - 1000 TON SPRING STARTUP (4 CELLS)		1	81.20	
HVAC-11.1	COOLING TOWERS 51 - 500 TON SPRING STARTUP (1 CELL)		1	10.15	
HVAC-11.1	COOLING TOWERS 51 - 500 TON SPRING STARTUP (2 CELLS)		1	20.30	
HVAC-11.1	COOLING TOWERS 51 - 500 TON SPRING STARTUP (3 CELLS)		1	30.45	
HVAC-11.1	COOLING TOWERS 51 - 500 TON SPRING STARTUP (4 CELLS)		1	40.60	
HVAC-11.1	COOLING TOWERS <= 50 TON SPRING STARTUP (1 CELL)		1	4.90	
HVAC-11.1	COOLING TOWERS <= 50 TON SPRING STARTUP (2 CELLS)		1	9.80	
HVAC-11.1	COOLING TOWERS <= 50 TON SPRING STARTUP (3 CELLS)		1	14.70	
HVAC-11.1	COOLING TOWERS <= 50 TON SPRING STARTUP (4 CELLS)		1	19.60	
HVAC-11.1	COOLING TOWERS > 1000 TON SPRING STARTUP (1 CELL)		1	26.95	
HVAC-11.1	COOLING TOWERS > 1000 TON SPRING STARTUP (2 CELLS)		1	53.90	
HVAC-11.1	COOLING TOWERS > 1000 TON SPRING STARTUP (3 CELLS)		1	80.85	
HVAC-11.1	COOLING TOWERS > 1000 TON SPRING STARTUP (4 CELLS)		1	107.80	
HVAC-11.2	COOLING TOWERS 501 - 1000 TON FALL SHUTDOWN (1 CELL)		1	8.70	
HVAC-11.2	COOLING TOWERS 501 - 1000 TON FALL SHUTDOWN (2 CELLS)		1	17.40	
HVAC-11.2	COOLING TOWERS 501 - 1000 TON FALL SHUTDOWN (3 CELLS)		1	26.10	
HVAC-11.2	COOLING TOWERS 501 - 1000 TON FALL SHUTDOWN (4 CELLS)		1	34.80	
HVAC-11.2	COOLING TOWERS 51 - 500 TON FALL SHUTDOWN (1 CELL)		1	4.35	
HVAC-11.2	COOLING TOWERS 51 - 500 TON FALL SHUTDOWN (2 CELLS)		1	8.70	
HVAC-11.2	COOLING TOWERS 51 - 500 TON FALL SHUTDOWN (3 CELLS)		1	13.05	
HVAC-11.2	COOLING TOWERS 51 - 500 TON FALL SHUTDOWN (4 CELLS)		1	17.40	
HVAC-11.2	COOLING TOWERS <= 50 TON FALL SHUTDOWN (1 CELL)		1	2.10	
HVAC-11.2	COOLING TOWERS <= 50 TON FALL SHUTDOWN (2 CELLS)		1	4.20	
HVAC-11.2	COOLING TOWERS <= 50 TON FALL SHUTDOWN (3 CELLS)		1	6.30	
HVAC-11.2	COOLING TOWERS <= 50 TON FALL SHUTDOWN (4 CELLS)		1	8.40	

Figure 3-8. PS Form 4896A, Page 1 of 4 – Annual Standard Requirement Building Preventive Maintenance

TABLE A: HVAC					
GUIDE NO.	TASK DESCRIPTION	QUANTITY	FREQUENCY (per year)	WORK HOURS (per freq)	TOTAL WORK HOURS
HVAC-11.2	COOLING TOWERS > 1000 TON FALL SHUTDOWN (1 CELL)		1	11.55	
HVAC-11.2	COOLING TOWERS > 1000 TON FALL SHUTDOWN (2 CELLS)		1	23.10	
HVAC-11.2	COOLING TOWERS > 1000 TON FALL SHUTDOWN (3 CELLS)		1	34.65	
HVAC-11.2	COOLING TOWERS > 1000 TON FALL SHUTDOWN (4 CELLS)		1	46.20	
HVAC-12	FAN, CENTRIFUGAL <7HP		1	1.75	
HVAC-12	FAN, CENTRIFUGAL >=7HP		1	2.75	
HVAC-13	FILTERS, ROLL-TYPE, DISPOSABLE MEDIA		4	1.75	
HVAC-14	CONTROLS AND MECHANISMS ROLL TYPE FILTERS		1	1.50	
HVAC-15	FILTERS, THROW-AWAY		4	0.10	
HVAC-16	FAN, PROPELLER, PEDESTAL AND WALL MOUNTED		1	0.75	
HVAC-17	HEAT/COOLING UNIT, ROOF TOP		2	8.50	
HVAC-18	REFRIGERATION MACHINES, ABSORPTION TYPE <= 40 TONS		1	15.25	
HVAC-18	REFRIGERATION MACHINES, ABSORPTION TYPE 41 - 100 TONS		1	19.25	
HVAC-18	REFRIGERATION MACHINES, ABSORPTION TYPE 101 - 400 TONS		1	23.00	
HVAC-18	REFRIGERATION MACHINES, ABSORPTION TYPE > 400 TONS		1	30.75	
HVAC-19	REFRIGERATION MACHINES (CENTRIFUGAL AND RECIPROCATING) <= 40 TONS		1	23.00	
HVAC-19	REFRIGERATION MACHINES (CENTRIFUGAL AND RECIPROCATING) 41 - 100 TONS		1	31.00	
HVAC-19	REFRIGERATION MACHINES (CENTRIFUGAL AND RECIPROCATING) 101 - 350 TONS		1	39.00	
HVAC-19	REFRIGERATION MACHINES (CENTRIFUGAL AND RECIPROCATING) 351 - 500 TONS		1	59.00	
HVAC-19	REFRIGERATION MACHINES (CENTRIFUGAL AND RECIPROCATING) 501 - 750 TONS		1	66.00	
HVAC-19	REFRIGERATION MACHINES (CENTRIFUGAL AND RECIPROCATING) 751 - 1000 TONS		1	77.00	
HVAC-19	REFRIGERATION MACHINES (CENTRIFUGAL AND RECIPROCATING) > 1000 TONS		1	96.00	
HVAC-20	HEATER, ELECTRIC, IN-DUCT		1	0.25	
HVAC-21	HEATER, ELECTRIC, BASEBOARD		1	0.15	
HVAC-22	UNIT HEATERS (STEAM AND HOT WATER)		1	1.00	
HVAC-23	UNIT HEATERS (GAS FIRED)		1	1.50	
HVAC-24	FIRE DAMPERS (IN DUCT)		1	0.20	
HVAC-25	SPLIT SYSTEM EVAPORATOR UNITS (ANNUAL)		1	4.00	
HVAC-26	SPLIT SYSTEM EVAPORATOR UNITS (MONTHLY)		12	0.50	
	SUBTOTAL				

TABLE B: ELEC					
GUIDE NO.	TASK DESCRIPTION	QUANTITY	FREQUENCY (per year)	WORK HOURS (per freq)	TOTAL WORK HOURS
ELEC-1	MOTORS		1	1.00	
ELEC-2	BACK-UP GENERATOR- GAS OR NATURAL GAS ENGINES		1	2.00 to 6.00	
ELEC-3	EMERGENCY GENERATORS, DIESEL POWER		1	3.00 to 8.00	
ELEC-4	GENERATORS, ALL TYPES		12	1.00 to 2.00	
ELEC-5	PANEL, ELECTRICAL (INFRARED SCAN)		1	0.15	
	SUBTOTAL				

TABLE C: PLUM

Figure 3-9. PS Form 4896A, Page 2 of 4 – Annual Standard Requirement Building Preventive Maintenance

GUIDE NO.	TASK DESCRIPTION TABLE C: PLUM	QUANTITY	FREQUENCY (per year)	WORK HOURS (per freq)	TOTAL WORK HOURS
GUIDE NO.	TASK DESCRIPTION	QUANTITY	FREQUENCY (per year)	WORK HOURS (per freq)	TOTAL WORK HOURS
PLUM-1	FIRE EXTINGUISHER, PORTABLE, STORED-PRESSURE		1	0.10	
PLUM-2	SUMP PUMPS		1	3.75	
PLUM-3	VALVES, REGULATING		1	1.00 to 4.00	
PLUM-4	VALVES, MANUALLY OPERATED (MAIN LINE)		1	1.00	
PLUM-4	VALVES, MANUALLY OPERATED (OTHER VALVES OVER 2 INCHES)		0.2	0.50	
PLUM-5	VALVES, MOTOR OPERATED		1	1.50	
PLUM-6	STEAM TRAPS, ALL TYPES		1	0.50	
PLUM-7	PUMPS, CENTRIFUGAL >=25HP		1	6.00	
PLUM-7	PUMPS, CENTRIFUGAL >5HP AND <25HP		1	4.00	
PLUM-8	ROOF, INSPECTION		2	1.00 to 2.00	
PLUM-9	HOT WATER HEATERS (CONVERTERS)		1	4.50	
PLUM-10	HOT WATER HEATERS, DOMESTIC TYPE		1	1.50	
PLUM-11	FIRE PUMPS, ELECTRIC MOTOR DRIVE		1	0.75	
PLUM-12	FIRE PUMPS, INTERNAL COMBUSTION ENGINE DRIVE		1	0.75 to 1.50	
PLUM-13	DRINKING WATER COOLERS		1	1.00	
PLUM-14	EYEWASH, PLUMBED		1	0.30	
PLUM-15	SHOWERS, EMERGENCY		1	0.30	
	SUBTOTAL				

TABLE D: EMS					
GUIDE NO.	TASK DESCRIPTION	QUANTITY	FREQUENCY (per year)	WORK HOURS (per freq)	TOTAL WORK HOURS
EMS-5	EMERGENCY GENERATORS		12	1.00 to 2.00	
EMS-6	FIRE ALARM BOXES (MANUAL)		4 to 6	0.10	
	SUBTOTAL				

TABLE E: MISC					
GUIDE NO.	TASK DESCRIPTION	QUANTITY	FREQUENCY (per year)	WORK HOURS (per freq)	TOTAL WORK HOURS
MISC-1	AIR COMPRESSORS		1	1.00	
MISC-2	LAWNMOWERS AND EDGERS		2	1.00	
MISC-3	SWEEPERS (GASOLINE)		2 to 6	2.00	
MISC-4	PAPER BALERS		1	3.00	
MISC-5.1	DOCK DOORS, POWER OPERATED		2	2.00	
MISC-5.2	DOCK DOORS, MANUAL OPERATED		2	1.00	
MISC-6	DOOR, PEDESTRIAN DOORS, POWER OPERATED MAIN AND DOCK ENTRANCES		4	1.00	
MISC-7	DOOR, PEDESTRIAN DOORS, NON-POWERED MAIN AND DOCK ENTRANCE		2	1.00	
MISC-8	DOCK LEVELERS, POWERED		4	1.25	
MISC-9	FIRE DOORS, STAIRWELLS AND EXITWAYS (SWINGING)		4	0.10	
MISC-10	FIRE DOORS, SLIDING TYPE		4	0.10	
MISC-11	STATIONARY PACKERS (WEEKLY)		52	1.00	
MISC-12	STATIONARY PACKERS (MONTHLY)		12	1.00	
MISC-13	STATIONARY PACKERS (QUARTERLY)		4	2.00	
MISC-14	POWER LIFTS		12	1.00	
MISC-15	SNOW BLOWER, WALKING TYPE		1	1.00	

Figure 3-10. PS Form 4896A, Page 3 of 4 – Annual Standard Requirement Building Preventive Maintenance

TABLE E: MISC					
GUIDE NO.	TASK DESCRIPTION	QUANTITY	FREQUENCY (per year)	WORK HOURS (per freq)	TOTAL WORK HOURS
MISC-16	DOCK LEVELERS, MANUAL		4	0.50	
MISC-17	SWEEPERS (BATTERY)		4 to 12	1.00	
MISC-18	FLOOR SCRUBBERS, AUTOMATIC; VACUUM, BATTERY POWERED		4 to 12	1.00	
MISC-19	BATTERY, PIV, FLOODED LEAD ACID		2	0.30	
MISC-20	TRAILER RESTRAINTS - QUARTERLY		4	1.00	
MISC-21	TRAILER RESTRAINTS - ANNUAL		1	0.50	
MMO09615	PIVMS VAC (MONTHLY)		12	0.55	
MMO09615	PIVMS VAC (QUARTERLY)		4	0.52	
MMO03718	COMPACTOR, PTR		1	27.89	
MMO03218	COMPRESSED AIR LEAK SURVEY		1	0.00 to 24.00	
MMO09520	S6 PALLET JACK - 5 DAY		260	0.31	
MMO09520	S6 PALLET JACK - 6 DAY		312	0.30	
MMO09520	S6 PALLET JACK - 7 DAY		364	0.30	
MMO09620	DAIFUKU PALLET JACK 5 DAY		260	0.32	
MMO09620	DAIFUKU PALLET JACK 6 DAY		312	0.31	
MMO09620	DAIFUKU PALLET JACK 7 DAY		364	0.31	
MMO09720	DAIFUKU TOW MOTOR 5 DAY		260	0.32	
MMO09720	DAIFUKU TOW MOTOR 6 DAY		312	0.31	
MMO09720	DAIFUKU TOW MOTOR 7 DAY		364	0.31	
MMO09820	SEEGRID TOW MOTOR 5 DAY		260	0.28	
MMO09820	SEEGRID TOW MOTOR 6 DAY		312	0.27	
MMO09820	SEEGRID TOW MOTOR 7 DAY		364	0.27	
MMO16619	HOIST, 5 DAY OPERATION		260	0.15	
MMO16619	HOIST, 6 DAY OPERATION		312	0.15	
MMO16619	HOIST, 7 DAY OPERATION		364	0.15	
MMO16619	HOIST, MONTHLY		12	0.15	
MMO16619	HOIST, SEMI-ANNUAL (ALL)		2	0.93	
MMO16619	HOIST, SEMI-ANNUAL (PENTHOUSE)		2	0.15	
MMO16619	HOIST, WEEKLY		52	0.15	
	FORKLIFT		1	50.00	
	PALLET TRUCK, MOTORIZED		1	50.00	
	PALLET TRUCK, NON MOTORIZED		1	1.00	
	TOW TRACTOR		1	52.00	
	SUBTOTAL				

PS FORM 12/28/2018 **4896A - BLANK FORM**

Figure 3-11. PS Form 4896A, Page 4 of 4 – Annual Standard Requirement Building Preventive Maintenance

Chapter 5 – Field Maintenance Staffing Package

EXPLANATION OF FIELD MAINTENANCE STAFFING

Field Maintenance Staffing (AMT, AMS) is determined by “summing the hours from the last 13 accounting periods.” This is known as using historical data to determine staffing and includes time (and overtime) spent working in the domicile office, area offices, FMO work performed by non-FMO employees, travel time, time spent completing paperwork, etc.

A one-year history eMARS *Work Order and PM Reports*, as well as the field maintenance employees’ daily work assignment sheets (or any personal records kept by individual field maintenance employees) will be help challenge reductions in field maintenance positions.

SAMPLE FIELD MAINTENANCE STAFFING DOCUMENT

This guide includes a sample Field Maintenance Staffing document.

FIELD MAINTENANCE PROGRAM
STAFFING SUMMARY

XXXXXX

WHEP Version 2.1

Provide the data indicated by summing the hours from the last 13 consecutive accounting periods:

LINE		
1.	FMO Repairs performed at Home office	0.00
2.	Work Performed at Associate post Offices	0.00
3.	FMO plus "Other" Overtime	0.00
4.	FMO Work by Non-FMO Personnel	0.00
5.	Work Performed at other FMO's	0.00
6.	Sum lines 1 + 2 + 3 + 4 + 5 (Productive Work) - Subtotal	0.00
7.	FMO Travel Time	0.00
8.	FMO Travel by Non-FMO Personnel	0.00
9.	Record keeping, etc. by FMO Only	0.00
10.	Sum lines 7 + 8 + 9 (Other Workhours) - Subtotal	0.00
11.	Sum lines 6 + 10	0.00
12.	Multiply line 11 by 1.1 (TOTAL WORKHOURS) (Adds 10% for Modifications, Alterations and Training)	0.00
13.	Divide line 12 by 1760 = Man Years Required	0.00

1752 now, Juneteenth holiday.

An employee excessed from their occupational group retains retreat rights to that occupational group irrespective of whether that employee has an in-craft MSS rating.

Current Maintenance Craft employees who are reassigned pursuant to Article 12.5.C.4 (cross section within the craft and installation) retain retreat rights to their former section (occupational group and as identified in their LMOU). The application of their retreat rights, in this specific instance, occurs following the use of the PAR in the section (identified in their LMOU) from which they were excessed and immediately prior to using the PER.

Article 38.4

A Maintenance Craft Notice of Intent is posted and the duty assignment filled from within the installation where the vacancy exists. This location is where the employee is normally expected to begin and end tour.

e.g. - an Area Maintenance Technician (AMT) has their work hours assigned to a Field Maintenance District Office. The AMT begins tour at a 'domicile' office. That 'domicile' office is the AMT's official duty station for purposes of application of the Collective Bargaining Agreement and is where PAR and PER for that AMT duty assignment are established and utilized. This should be indicated on the employee's PS Form 50 lines 35-36 showing the employee's Duty Station and lines 32-34 can indicate a different Employ Office.

Article 38.4.A.1

POSTING – NOTICE OF INTENT

Article 38.4.A.1 provides for the following:

- The posting of a Notice of Intent to fill vacant or newly established duty assignments.
- Notices of Intent are posted for a period of seven (7) calendar days.
- A copy of the Notice of Intent shall be furnished to the Local Union.
- A duty assignment will be filled using the appropriate preferred assignment selection register and/or promotion eligibility register.
- An employee on sick leave or off-site training on the day of the posting shall be furnished a copy of any applicable Notice of Intent.
- An employee who is absent on annual leave and who has submitted a written request, stating the employee's mailing address, will be provided a copy of any applicable Notice of Intent by mail.

If an employee has been granted leave without pay (LWOP), determining whether an employee is automatically provided a copy of the Notice of Intent (NOI) or whether the employee must request a copy of the NOI is based on the paid leave category that the employee was otherwise eligible for. Examples:

- An employee who is off work due to illness or injury on the day of the posting elects to use LWOP instead of sick leave. The NOI would be provided to the employee.

- An employee who takes LWOP instead of annual leave is required to make written request for a copy of the NOI.

ATTACHMENT 1

ELECTRONIC WORK HOUR ESTIMATOR PROGRAM OVERVIEW

1.0 GENERAL

a. The electronic Work Hour Estimator Program (eWHEP) calculates staffing packages for all plants (PDC, NDC, and all other maintenance capable facilities) including the subordinate facilities associated with them such as: stations, branches, Air Mail Centers, annexes, etc.

b. Local management, with Headquarters Maintenance Operations concurrence, can adjust work hour allowances provided in the eWHEP program in response to local conditions. For mail processing equipment, adjustments can be based on factors such as: number, age, general condition of the machines; the usage by mail processing operations; the maintenance window's length and, the variety of non-standard processing equipment. For buildings and building equipment, local conditions such as geographic area, climate, customer/employee activity, type of construction, building age or unique equipment may be considered.

c. The eWHEP estimates work hours by employee level, uses the "minimum skill level" provided by existing approved MMOs, and allows users to assign levels when approved MMOs do not exist.

2.0 SCOPE

The eWHEP:

- Is for use in plants (both PDC and NDC), stations, branches, annexes, airmail facilities, and all other maintenance capable facilities.
- Provides the means to estimate workhours for Mail Processing Equipment (Miscellaneous Postal Equipment and Major Equipment), Field Maintenance Operations (FMO), and Maintenance Operations Support (MOS).
- FMO Staffing Worksheet includes building and building related equipment work hours for supported offices such as Station/Branches and Associate Offices (AO) within the FMO framework.
- Does not estimate workhours for Building Services, but accepts and displays data from other sources to provide a complete work hour summary of a given facility.
- Does not estimate workhours for Building Equipment or structure, but accepts and displays data from other sources to provide a complete work hour summary of a given facility.

eWHEP software calculates staffing hours for maintaining Mail Processing Equipment (MPE) platforms based on published maintenance support documentation. For MPE platforms currently lacking Article 19 approved maintenance support documentation, local management will add those platforms as an exception under a page (form) in the staffing software called Section 2C “Other Requirements”.

Field Maintenance Operations (FMO)

Utilize historical FMO work hours to calculate annual FMO staffing. Historical hours are now found in both register x20 and register x50. The staffing module calculates and forwards totals to the appropriate summaries.

Maintenance Support Clerk

The eWHEP calculates the number of recommended Maintenance Support Clerk (MSC) positions based on the latest updated Staffing Criteria for MSC positions listed in Table 1-1.

Table 1-1. Staffing Criteria for MSC

Number of positions	0-19	20-39	40-59	60-79	80-100	101-125	126-150	151-175	176-200	201-225	226-250	251-285
MSC Positions Authorized	0	1	2	3	4	5	6	7	8	9	10	11
Number of positions supported	286-320	321-355	356-390	391-425	426-460	461-495	496-530	531-565	566-600	601-635	636-670	671-705
MSC Positions Authorized	12	13	14	15	16	17	18	19	20	21	22	23

In addition to the number of recommended MSC positions based on the above chart, NDCs are allocated one (1) additional MSC position provided there are at least 20 maintenance positions supported.

Number of positions supported calculation in the eWHEP does not include Station/Branch maintenance personnel.

The local site may request a variance to the Maintenance Support Clerk staffing chart, adding one additional Maintenance Support Clerk position. The Area Office will consider the request and, based on site-specific requirements, may approve one additional Maintenance Support Clerk position.

Chapter 6 – Maintenance Support Clerk Staffing

EXPLANATION OF MAINTENANCE SUPPORT CLERK STAFFING

Maintenance Support Clerk staffing is determined using the staffing matrix in MMO-102-18 and is based on the “number of supported positions” within the installation. For example, using the staffing matrix, if there are between 20-39 “supported positions” within the installation, one (1) Maintenance Support Clerk is authorized.

Note that in applying the MMO-102-18 staffing matrix “supported positions” excludes Maintenance Craft employees working in stations and branches, Maintenance EAS employees (the APWU lost that in a national level dispute), and Maintenance Support Clerks.

SAMPLE MAINTENANCE SUPPORT CLERK STAFFING MATRIX (MMO-102-18)

This guide includes a copy of MMO-102-18.

eWHEP software calculates staffing hours for maintaining Mail Processing Equipment (MPE) platforms based on published maintenance support documentation. For MPE platforms currently lacking Article 19 approved maintenance support documentation, local management will add those platforms as an exception under a page (form) in the staffing software called Section 2C "Other Requirements".

Field Maintenance Operations (FMO)

Utilize historical FMO work hours to calculate annual FMO staffing. Historical hours are now found in both register x20 and register x50. The staffing module calculates and forwards totals to the appropriate summaries.

Maintenance Support Clerk

The eWHEP calculates the number off recommended Maintenance Support Clerk (MSC) positions based on the latest updated Staffing Criteria for MSC positions listed in Table 1-1.

Table 1-1. Staffing Criteria for MSC

Number of positions	0-19	20-39	40-59	60-79	80-100	101-125	126-150	151-175	176-200	201-225	226-250	251-285
MSC Positions Authorized	0	1	2	3	4	5	6	7	8	9	10	11
Number of positions supported	286-320	321-355	356-390	391-425	426-460	461-495	496-530	531-565	566-600	601-635	636-670	671-705
MSC Positions Authorized	12	13	14	15	16	17	18	19	20	21	22	23

In addition to the number of recommended MSC positions based on the above chart, NDCs are allocated one (1) additional MSC position provided there are at least 20 maintenance positions supported.

Number of positions supported calculation in the eWHEP does not include Station/Branch maintenance personnel.

The local site may request a variance to the Maintenance Support Clerk staffing chart, adding one additional Maintenance Support Clerk position. The Area Office will consider the request and, based on site-specific requirements, may approve one additional Maintenance Support Clerk position.

Chapter 7 – Maintenance Vacancies & Article 38.3.K.4

EXPLANATION OF NEW LANGUAGE (2015-2018 CBA) in ARTICLE 38.3.K.4

New language in the 2015-2018 Collective Bargaining Agreement (Article 38.3.K.4) provides additional protection from involuntary reassignments in the event there are lower level vacant maintenance craft duty assignments. The new language states:

38.3.K.4

A Maintenance Craft employee being considered for excessing under Article 12 will not be excessed if a vacant lower level position exists and:

a. The vacant lower level position is supported by the current approved staffing package, and

b. The duties and responsibilities of the vacant lower level position are encompassed by the employee's current position as per the following:

i. Electronic Technician (ET) PS-10 encompasses Mail Processing Equipment Mechanic (MPE) PS-9 and Maintenance Mechanic (MM) PS-7;

ii. Mail Processing Equipment Mechanic (MPE) PS-9 and Building Equipment Mechanics (BEM) PS-9 encompass Maintenance Mechanic (MM) PS-7.

c. If the excessing is occurring under Article 12.5.C.4, item b above will be applied on a tour-wide basis.

RFIs must be submitted requesting a complete listing of all vacant maintenance craft duty assignments within the installation for the purpose of possibly avoiding the excessing of employee(s).

The regional coordinator and national business agent(s) must be updated of any vacancies occurring subsequent to the initial inquiry.

Chapter 8 – Overtime Usage and the CWHR

While the initial impact reports may identify an extraordinary amount of overtime used prior to the involuntary reassignment(s) and after, management often argues that this data is not just reflective of the affected occupational groups but *all* occupational groups in the Maintenance Craft within the installation.

Copies of overtime reports identifying all overtime and penalty overtime hours worked exclusively by the affected occupational group during the previous twelve months must be requested to provide a more accurate account of exactly how much overtime was worked.

Assuming employees are excessed outside of their craft and/or installation, 45 days after any involuntary reassignments, the regional coordinator will be provided with the CWHR (Comparative Work Hour Report). The JCIM clarifies:

> *This report no longer has to be requested by the Union. When employees are excessed out of their craft or installation, the Union at the regional level shall be provided with a comparative work hour report of the losing craft or installation forty-five (45) days, whenever possible, after the excessing of any APWU represented employee outside either their craft or their installation.*
>
> *The report provides a listing of all work hours used on a daily basis in the affected craft for the period of thirty days before and thirty days after the reassignments. If the report does not indicate that conditions warranted the reassignments, the retreat rights of the affected employees shall be activated. If the retreat rights are denied, the employees have the right to initiate a grievance pursuant to Article 15.*

The regional coordinator and national business agent will review the comparative work hour report and, if sufficient overtime has been worked post-excessing, the excessed employee(s) must be offered retreat rights.

Chapter 9 – Miscellaneous Mitigating Factors

In an effort to mitigate or negate the impact of an Article 12 event, RFIs must be submitted to identify the following:

Ensure MOPE / PIT Equipment is in Correct Inventory

Identify which occupational group(s) historically performed maintenance on MOPE/PIT equipment within the installation. If LDC37 employees (BEM) have performed the maintenance, ensure the MOPE/PIT equipment is in the MS-1 staffing package inventory. If LDC36 employees (ET, MPE, MM7) have performed the work, ensure the MOPE/PIT equipment is in the eWHEP/Mechanized staffing package. However, understand that this is simply a shell game. The shifting of annual staffing hours from one inventory to another will not only result in an increase in the gaining inventory, but also a loss of annual staffing hours in the losing inventory.

Non-Maintenance Craft Limited Duty Employees in the Maintenance Craft

Page 103 of the 2017 JCIM (Joint Contract Interpretation Manual) requires that limited duty employees temporarily assigned to the craft undergoing excessing, be returned to their respective crafts before excessing occurs. Submit an RFI requesting that all ill or injured employees reassigned into, and currently in, the Maintenance Craft within the installation be identified.

Maintenance Craft Employees with Pending eReassign Transfer Requests

Page 299 of the Collective Bargaining Agreement contains the MOU Re: Transfer Opportunities to Minimize Excessing which elevates Maintenance Craft employees within impacted installations to the top of the eReassign transfer list in a priority transfer status. This applies to all Maintenance Craft employees within the impacted installation, not just Maintenance Craft employees within the affected occupational groups. Submit an RFI to identify all Maintenance Craft employees within the installation with live/pending transfer requests outside of the installation. If a sufficient number of priority transfer requests are granted, the argument may be made that the reduction should occur through attrition.

Retirement-Eligible Maintenance Craft Employees

For obvious reasons, retirement-eligible Maintenance Craft employees within the impacted installation may possibly mitigate an excessing event. Submit an RFI to identify all retirement-eligible Maintenance Craft employees within the installation so that an argument may be made that the reduction should occur through attrition.

APWU
1300 L Streeet NW, Washington DC, 20005
MAINTENANCE DIVISION




TABLE OF CONTENTS

1. Introduction & Quick Instructions - Pages 1-3
2. Information Requests - Pages 4-5
3. Acquiring CSV WebEOR Reports - Pages 6-9
4. Installing Python On Computer - Pages 10-13
5. Tours Calculation Program & Results - Pages 14-17
6. Troubleshooting & Help - Page 18

INTRODUCTION

In 2017, the Postal Service changed the method in which the number of operational tours were entered into eWHEP for major mechanization staffing purposes. Instead of local management having sole control of manually entering into eWHEP the number of tours major mechanization was in operation, the Postal Service unilaterally implemented a program that precluded local management from manually entering the number of operational tours in eWHEP for several types of mail processing equipment, and replaced it with a program that automatically populated the number of tours field and precluded local management from making that decision.

APWU initiated a national dispute on this issue and laid two challenges. First, that it was a violation to implement this new change without notification and discussion with the national union and, second, that this change now removed local management's ability to determine the number of operational tours based on local experience and fact circumstance. The arbitrator ruled that the Postal Service was not obligated to notify the national union, and that local management still had the ability to request additional operational tour staffing hours using the 2C form. Fortunately, this arbitration decision did not affect the right of local unions to continue to challenge the accuracy of their eWHEP staffing packages and whether they were receiving sufficient staffing hours for the number of operational tours.

Investigating this type of violation took weeks of analyzing thousands of pages of machine run time reports by hand, notating how many hours each individual machine was in operation on any given tour and day over a year. Needless to say, it was time consuming and labor intensive. In an effort to save time and spare local unions the grief involved in analyzing that much data, the APWU developed this program – The eWHEP Tours Calculation Program.

This user guide is intended to explain the issue and assist local unions in requesting the correct information and reports, importing the data into the program and analyzing the summary results to determine if a violation exists.

QUICK INSTRUCTIONS

More detailed instructions on requesting information and acquiring reports in CSV format and running the eWHEP Tours Calculation Program begin on page 4.

Step 1: Submit Information Requests & Acquire WebEOR Reports, Staffing Package, etc.

Step 2: Create a folder on your computer (does not matter what it is named)

Step 3: Create another folder inside the folder just created, name new folder "Data"

Step 4: Save all WebEOR reports in the single folder named "Data"

Step 5: Make sure all files associated with program are in the original folder created

Step 6: Install Python and Modules on your PC following the directions in this Guide

Step 7: Run the Tours Calculation Program and analyze the Summary

After Step 7 is complete (which may take 5 minutes to process), the "Summary" and "Output" documents will be generated for your review, and will contain the average number of tours that each individual machine was in operation during the 365-day period that the WebEOR reports reflect.

INFORMATION REQUESTS

In order to get accurate results using the program, local unions must ensure that the information and reports that are requested are correct. The reports exist in one-week blocks, so the union will need to request 52 separate reports (one for each week) for the past year. These reports must also be provided in .CSV (comma separated value) format in order for the program to process the information.

Below is a sample information request for the data the union needs:

1. *Management to provide copies of all WebEOR reports for the past 52 weeks that identifies machine run time data for all major mechanization within the installation. This information to be provided digitally and in .CSV format.*

2. *Management to provide copies of the current, approved eWHEP staffing package (to include all forms).*

3. *Management to provide copies of all current eMARS staffing worksheets for all major mechanization within the installation.*

In the event management claims ignorance and is unable to provide the requested WebEOR reports, the following page contains detailed screen shots using an ACE computer describing where to go and what to click in order to access and furnish the union's requested information.

Template Information Request is on the following page for you to print and fill out.

American Postal Workers Union AFL-CIO

INFORMATION REQUEST

CLASS ACTION OR PERSON (Last Name First)	NATURE OF ALLEGATION
CLASS ACTION	eWHEP STAFFING INACCURACY

DATE OF REQUEST

TO: _____ TITLE: _____

FROM: _____ TITLE: _____

SUBJECT: REQUEST FOR INFORMATION AND DOCUMENTATION RELATIVE TO PROCESSING A GRIEVANCE


We request that the following documents and/or witnesses be made available to us in order to properly identify whether or not a grievance does exist and, if so, their relevancy to the grievance:

	Information provided ? YES	NO
1. Management to provide copies of all WebEOR reports for the past 52 weeks that identifies machine run time data for all major mechanization within the installation. This information to be provided digitally and in .CSV format.	( )	( )
2. Management to provide copies of the current, approved eWHEP staffing package (to include all forms).	( )	( )
3. Management to provide copies of all current eMARS staffing worksheets for all major mechanization within the installation.	( )	( )
4. Complete, current list of all mail processing equipment inventory within the installation. If any new equipment was installed within the past year, identify the date(s) of installation and beginning operation.	( )	( )

Article 17, Section 3 requires the Employer to provide for review all documents, files, and other records necessary in processing a grievance. Article 31, Section 3, requires that the Employer make available for inspection by the Unions all relevant information necessary for collective bargaining or the enforcement, administration or interpretation of this Agreement. Under 8 a (5) of the National Labor Relations Act it is an Unfair Labor Practice for the Employer to fail to supply relevant information for the purpose of collective bargaining. Grievance processing is an extension of the collective bargaining process.


ACQUIRING CSV WEBEOR REPORTS

On an ACE computer, locate and click the 'green folder' icon along the top of the page, and then local ate select 'WebEOR' from the drop-down menu. Once the WebEOR page loads, click the 'Enter Application' button to enter WebEOR.




ACQUIRING CSV WEBEOR REPORTS

Once inside the WebEOR program, use the drop-down menu to select which site the union is requesting information and reports for.




ACQUIRING CSV WEBEOR REPORTS

After selecting which site you need data for, click the “EOR Viewer” link in the far left column of the Main Menu.



ACQUIRING CSV WEBEOR REPORTS

After clicking the “EOR Viewer” link, select the date range that the union needs the reports to show. Keep in mind that the maximum date range allowable is one week. Once the date range is selected, click the “refresh data” button, and then select the “CSV” link at the upper left-hand corner for the .CSV version of the report being requested. This will need to be done 52 times, because the program only allows for a maximum range of one week’s data.



INSTALLING PYTHON ON YOUR COMPUTER

Once the union has acquired the 52 weeks of individual .CSV reports, create a folder on your computer (doesn't matter what it is named). Inside the folder you just created, create another folder named "Data" and put all of the .CSV reports in to the Data folder.

All of the Tours Calculation Program files must also be placed into the original folder that you created (not the Data folder). Once this has happened, it is time to install Python and the Python Modules. To do this:


First, run the "Install Python" file and then the following screens will appear (be sure that "Add Python 3.10 to Path" is selected).

Click "Install Now"




INSTALLING PYTHON ON YOUR COMPUTER

Once “Install Now” is clicked, Python will begin the process of being installed on your computer and will show the screen below with installation progress bar moving.



INSTALLING PYTHON ON YOUR COMPUTER


The installation process will take a few minutes. Once the installation is complete, you will see the option and must click “Close” as shown below, and also close the command window.



INSTALLING PYTHON ON YOUR COMPUTER

After clicking “Close” and the installation is complete, you must now install the Python modules. To do this, you must:


Run the “Install Python Modules” file, which will begin the automated process of installing the modules on your computer and will look like the screen below.



RUNNING THE TOURS CALULATION PROGRAM & RESULTS

After the Python Modules have been installed, it is finally time to actually un and use the Tours Calculation Program – which is the file named “main.py.”


In order to run the Tours Calculation Program, you must first right-click on “main” and select “Edit with IDLE” and then select “Edit with IDLE 3.10 (64-bit).”



RUNNING THE TOURS CALULATION PROGRAM & RESULTS


Once selecting “Edit with IDLE” and then selecting “Edit with IDLE 3.10 (64-bit)” the program will open and look like the sample below.

Once the program opens, you will then need click the “Run” option at the top, and then select “Run Module.” This will immediately start the program running and it will import the reports and process the machine run time information.




RUNNING THE TOURS CALULATION PROGRAM & RESULTS

The program will look like the sample below when it is running, importing the reports and processing the information.




You will know the program is finished processing the machine run time data when you see “Done.” You can now close the program out completely and begin reviewing the results of the program which has just saved you weeks of hand-analyzing tens of thousands of pages of reports.



RUNNING THE TOURS CALULATION PROGRAM & RESULTS

Once the program is done running, it will generate two reports – "Output" and "Summary." These two documents are the result of the program and is what local unions will need to analyze and compare with their existing eMARS Staffing Worksheets to determine whether or not the staffing package is accurate.



There will also be a column for the user to type in the current number of tours based on the eMARS Staffing Worksheets for a side-by-side comparison.

	Tour 1	Tour 2	Tour 3	Total tours	Total days ran	Avg. tours per day	Current Package	Difference
ADUS-1	345	134	99	578	368	1.57	2	
AFCS200-2	29	13	213	255	339	0.75	1	
AFCS200-3	33	17	248	298	347	0.86	1	
AFCS200-4	36	20	301	357	359	0.99	1	
AFCS200-5	38	13	302	353	359	0.98	1	
AFCS200-6	29	9	281	319	350	0.91	1	
AFCS200-7	24	51	215	290	343	0.85	1	
AFSM100-1	343	369	370	1082	372	2.91	2	-1
AFSM100-2	363	369	371	1103	372	2.97	2	-1
APBS-1	262	176	275	713	370	1.93	2	
ATU-1	329	335	335	999	343	2.91	3	
ATU-2	355	365	360	1080	369	2.93	2	-1
CIOSS-11	197	342	265	804	367	2.19	2	
CIOSS-16	174	276	202	652	365	1.79	1	-1
DBCS-12	234	273	370	877	372	2.36	2	
DBCS-13	235	297	369	901	372	2.42	2	
DBCS-14	245	257	370	872	372	2.34	2	

TROUBLESHOOTING & HELP

Running the eWHEP Tours Calculation Program can be resource-intensive on computers.

Those unable to process the data or that have any other questions / concerns may contact the APWU and request assistance at:

MaintStaffing@apwu.org